

# LOAN DOCUMENT

PHOTOGRAPH THIS SHEET

①

DTIC ACCESSION NUMBER

LEVEL

INVENTORY

Interim Rpt for Bioventing Field.

DOCUMENT IDENTIFICATION

25 Feb 93

**DISTRIBUTION STATEMENT A**  
Approved for Public Release  
Distribution Unlimited

DISTRIBUTION STATEMENT

ACCESSION BOX

NTIS GRAM  
DTIC TRAC  
UNANNOUNCED  
JUSTIFICATION

☒  
☒

BY

DISTRIBUTION/

AVAILABILITY CODES

DISTRIBUTION

AVAILABILITY AND/OR SPECIAL

A-1

DISTRIBUTION STAMP

DATE ACCESSIONED

DATE RETURNED

20001215 093

REGISTERED OR CERTIFIED NUMBER

PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-FDAC

H  
A  
N  
D  
L  
E  
  
W  
I  
T  
H  
  
C  
A  
R  
E

**INTERIM REPORT**  
**February 25, 1993**

**FOR**

**BIOVENTING FIELD INITIATIVE**

**AT**

**HANSCOM AIR FORCE BASE, MASSACHUSETTS**

**to**

**Captain Catherine M. Vogel**  
**Department of the Air Force**  
**AL/EQ**  
**139 Barnes Drive**  
**Tyndall AFB, Florida 32403-5319**

**by**

**BATTELLE**  
**Columbus Operations**  
**505 King Avenue**  
**Columbus, Ohio 43201-2693**

*AQ M01-03-0547*

**DEFENSE TECHNICAL INFORMATION CENTER  
REQUEST FOR SCIENTIFIC AND TECHNICAL REPORTS**Title AFCEE Collection**1. Report Availability (Please check one box)**

- ☒ This report is available. Complete sections 2a - 2f.  
☐ This report is not available. Complete section 3.

**2a. Number of  
Copies Forwarded**1 each**2b. Forwarding Date**July/2000**2c. Distribution Statement (Please check ONE box)**

DoD Directive 5230.24, "Distribution Statements on Technical Documents," 18 Mar 87, contains seven distribution statements, as described briefly below. Technical documents MUST be assigned a distribution statement.

- ☒ DISTRIBUTION STATEMENT A: Approved for public release. Distribution is unlimited.
- ☐ DISTRIBUTION STATEMENT B: Distribution authorized to U.S. Government Agencies only.
- ☐ DISTRIBUTION STATEMENT C: Distribution authorized to U.S. Government Agencies and their contractors.
- ☐ DISTRIBUTION STATEMENT D: Distribution authorized to U.S. Department of Defense (DoD) and U.S. DoD contractors only.
- ☐ DISTRIBUTION STATEMENT E: Distribution authorized to U.S. Department of Defense (DoD) components only.
- ☐ DISTRIBUTION STATEMENT F: Further dissemination only as directed by the controlling DoD office indicated below or by higher authority.
- ☐ DISTRIBUTION STATEMENT X: Distribution authorized to U.S. Government agencies and private individuals or enterprises eligible to obtain export-controlled technical data in accordance with DoD Directive 5230.25, Withholding of Unclassified Technical Data from Public Disclosure, 6 Nov 84.

**2d. Reason For the Above Distribution Statement (in accordance with DoD Directive 5230.24)****2e. Controlling Office**HQ AFCEE**2f. Date of Distribution Statement  
Determination**15 Nov 2000**3. This report is NOT forwarded for the following reasons. (Please check appropriate box)**

- ☐ It was previously forwarded to DTIC on \_\_\_\_\_ (date) and the AD number is \_\_\_\_\_
- ☐ It will be published at a later date. Enter approximate date if known. \_\_\_\_\_
- ☐ In accordance with the provisions of DoD Directive 3200.12, the requested document is not supplied because: \_\_\_\_\_

Print or Type Name

Laura Peña

Signature

Laura Peña

Telephone

210-536-1431

(For DTIC Use Only)

AQ Number M01-03-0547

## TABLE OF CONTENTS

1.0 INTRODUCTION .....	1
1.1 Objectives .....	1
1.2 Site Descriptions .....	2
1.2.1 Building 1639 Site .....	2
1.2.2 Building 1812 Site .....	2
2.0 BUILDING 1639 .....	6
2.1 Chronology of Events and Site Activities .....	6
2.1.1 Groundwater Measurements .....	6
2.1.2 Soil Gas Survey .....	6
2.1.3 Vent Well, Monitoring Point, and Thermocouple Installation .....	8
2.1.4 Soil and Soil Gas Sampling and Analyses .....	10
2.1.5 Soil Gas Permeability and Radius of Influence .....	10
2.1.6 In Situ Respiration Test .....	10
2.2 Results and Discussion .....	12
2.2.1 Soil and Soil Gas Analyses .....	12
2.2.2 Soil Gas Permeability and Radius of Influence .....	12
2.2.3 In Situ Respiration Test .....	12
2.2.4 Bioventing Demonstration .....	16
3.0 BUILDING 1812 .....	18
3.1 Chronology of Events and Site Activities .....	18
3.1.1 Groundwater Measurements .....	18
3.1.2 Soil Gas Survey .....	18
3.1.3 Vent Well, Monitoring Point, and Thermocouple Installation .....	20
3.1.4 Soil and Soil Gas Sampling and Analyses .....	22
3.1.5 Soil Gas Permeability and Radius of Influence .....	22
3.2 Results and Discussion .....	22
3.2.1 Soil and Soil Gas Analyses .....	22
3.2.2 Soil Gas Permeability and Radius of Influence .....	24
3.2.3 Bioventing Demonstration .....	24
4.0 BACKGROUND AREA ACTIVITIES .....	24
5.0 FUTURE WORK .....	27
6.0 REFERENCE .....	30
APPENDIX A: TEST PLAN FOR HANSCOM AFB, MASSACHUSETTS .....	A-1
APPENDIX B: ANALYTICAL REPORT FOR BUILDING 1639, BUILDING 1812, AND BACKGROUND AREA .....	B-1
APPENDIX C: BUILDING 1639 SOIL GAS PERMEABILITY DATA .....	C-1



APPENDIX D: BUILDING 1639 IN SITU RESPIRATION TEST DATA .....	D-1
---	-----

APPENDIX E: BUILDING 1812 SOIL GAS PERMEABILITY DATA .....	E-1
--	-----

## LIST OF TABLES

Table 1. Initial Soil Gas Composition at Building 1639 .....	7
Table 2. Results From Soil and Soil Gas Analyses for BTEX and TPH at Building 1639 .....	13
Table 3. Results From Soil Chemistry Analyses at Building 1639 .....	14
Table 4. Results of Hyperventilate™ Soil Gas Permeability Analysis at Building 1639 .....	14
Table 5. Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at Building 1639 .....	16
Table 6. Initial Soil Gas Composition at Building 1812 .....	19
Table 7. Results From Soil Analyses for BTEX and TPH at Building 1812 .....	23
Table 8. Results From Soil Chemistry Analysis at Building 1812 .....	23
Table 9. Results of Hyperventilate™ Soil Gas Permeability Analysis .....	25
Table 10. Results From Soil Chemistry Analysis at Background Area .....	28

## LIST OF FIGURES

Figure 1. Schematic Diagram of Hanscom AFB .....	3
Figure 2. Schematic Diagram of Building 1639 at Hanscom AFB (GS - Soil Gas Survey Point; MP - Monitoring Point) .....	4
Figure 3. Schematic Diagram of Building 1812 at Hanscom AFB (GS - Soil Gas Survey Point; MP - Monitoring Point) .....	5
Figure 4. Cross Section of Vent Well and Monitoring Points at Building 1639 Showing Site Lithology and Construction Detail (not to scale) .....	9
Figure 5. Radius of Influence at Building 1639 .....	15
Figure 6. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point H1-MPB-5.0' .....	17
Figure 7. Cross Section of Vent Well and Monitoring Points at Building 1812 Showing Site Lithology and Construction Detail (not to scale) .....	21
Figure 8. Radius of Influence at Building 1812 .....	26
Figure 9. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at the Background Area .....	29

**INTERIM REPORT**  
**BIOVENTING FIELD INITIATIVE**  
**HANSCOM AIR FORCE BASE, MASSACHUSETTS**

**1.0 INTRODUCTION**

This report describes the activities conducted at Hanscom Air Force Base (AFB), Massachusetts, as part of the Bioventing Field Initiative for the U.S. Air Force Center for Environmental Excellence (AFCEE) and the Environmental Quality Directorate of the Air Force Armstrong Laboratory. This report summarizes the results from the first phase of the study at Hanscom AFB. First-phase activities include a soil gas survey, air permeability test, in situ respiration tests, and installation of bioventing systems. The specific objectives of this Bioventing Field Initiative are described in the following section. Each site at the base is discussed individually, followed by a description of site activities at the background area.

**1.1 Objectives**

The purpose of this Bioventing Field Initiative is to measure the soil gas permeability and microbial activity at a contaminated site in order to evaluate the potential application of bioventing technology to remediate the site. The specific test objectives are stated below.

- A small-scale soil gas survey will be conducted to identify an appropriate location for installation of the bioventing system. Soil gas from the candidate site should exhibit high total petroleum hydrocarbon (TPH) concentrations, relatively low oxygen concentrations, and relatively high carbon dioxide concentrations. An uncontaminated background location also will be identified.
- The soil gas permeability of the soil and the air vent (well) radius of influence will be determined. To measure these parameters, air will be withdrawn or injected for approximately 8 hours at vent wells located in contaminated soils. Pressure changes will be monitored in an array of monitoring points.
- Immediately following the soil gas permeability test, an in situ respiration test will be conducted. Air will be injected into selected monitoring points to

aerate the soils. The in situ oxygen utilization and carbon dioxide production rates will be measured.

- The data from the soil gas permeability and in situ respiration tests will be used to determine an air injection/withdrawal rate for the bioventing test. A blower will be selected, installed, and operated for 6 to 12 months, and periodic measurements of the soil gas composition will be made to evaluate the long-term effectiveness of bioventing.

## **1.2 Site Descriptions**

Hanscom AFB is located in Bedford, Massachusetts. A schematic diagram of the base is shown in Figure 1. The dashed lines on the map indicate the direction from the main gate to each test site. Site H1 and Site H2 refer to Building 1639 and Building 1812, respectively. Groundwater at Hanscom AFB generally is encountered at 3 to 8 feet. The sites chosen for the bioventing test initiative are Building 1639 and Building 1812. A brief description of the sites is provided in Sections 1.2.1 and 1.2.2. A detailed description of the test sites is provided in the Test Plan in Appendix A.

### **1.2.1 Building 1639 Site**

Building 1639 is the base fuel service station (Figure 2). There have been three reported petroleum releases (gasoline, #2 fuel oil, and waste lubricating oil) at this facility since November 1990. Soil contamination at Building 1639 ranges from 599 ppm to 4,400 ppm TPH.

### **1.2.2 Building 1812 Site**

The site at Building 1812 was the location of a heating oil fuel tank (Figure 3). Leakage occurred from the tank, resulting in soil contamination at this site. The tank was replaced recently, and soil TPH concentrations as high as 2,830 mg/kg have been reported.





Figure 1. Schematic Diagram of Hanscom AFB



**Figure 2. Schematic Diagram of Building 1639 at Hanscom AFB (GS - Soil Gas Survey Point; MP - Monitoring Point)**




Figure 3. Schematic Diagram of Building 1812 at Hanscom AFB (GS - Soil Gas Survey Point; MP - Monitoring Point)

## 2.0 BUILDING 1639

### 2.1 Chronology of Events and Site Activities

#### 2.1.1 Groundwater Measurements

One groundwater monitoring well (12BO3) was present at Building 1639. Groundwater level was measured at this well on September 30, 1992 and was recorded at 5.75 feet.

#### 2.1.2 Soil Gas Survey

A suitable site for the bioventing demonstration should have soil gas characteristics of high TPH, low oxygen, and high carbon dioxide concentrations. This composition of soil gas would indicate that oxygen-limiting conditions for microbial activity are present and that the introduction of air may enhance biodegradation of TPH.

On September 30, 1992, a limited soil gas survey was conducted at Building 1639. Soil gases were sampled by driving a 5/8-inch-diameter stainless steel probe into the soil with a hammer drill. Soil gas was withdrawn with a vacuum pump and analyzed for oxygen, carbon dioxide, and TPH.

Measurements of oxygen and carbon dioxide in the soil gas were made with a GasTech Model 32520X with oxygen and carbon dioxide ranges of 0 to 25%. The analyzer was calibrated daily against atmospheric oxygen, atmospheric carbon dioxide, a 10% oxygen calibration standard, and a 5% carbon dioxide calibration standard. TPH was measured with a GasTech Trace Techtor with TPH ranges from 0 to 100, 0 to 1,000, and 0 to 10,000 ppm. The GasTech Trace Techtor was calibrated daily against a 4,200 ppm hexane standard.

The soil gas probes were driven to depths ranging from 2.5 to 5.0 feet at several locations at Building 1639. Table 1 provides the initial concentrations of oxygen, carbon dioxide, and TPH for the various locations at Building 1639. Oxygen concentrations varied from 0.8 to 21%, whereas TPH concentrations ranged from 410 ppm to greater than 20,000 ppm. The oxygen concentrations in the soil gas indicate that some areas at this site are oxygen-limited and may respond to bioventing.

Table 1. Initial Soil Gas Composition at Building 1639

Soil Gas Survey (GS) Point	Depth (ft)	Oxygen (%)	Carbon Dioxide (%)	TPH (ppm)
GS-1	2.5	19.0	2.5	15,600
	5.0	20.2	0.70	6,000
GS-2	2.5	16.0 <sup>1</sup>	5.8	> 20,000
	5.0	2.0	18.5	> 20,000
GS-3	2.5	1.0	18.5	> 20,000
	5.0	3.0	17.0	> 20,000
GS-4	2.5	21.0 <sup>1</sup>	0.10	920
	5.0	1.0	23.0	> 20,000
GS-5	2.5	16.2	5.8	660
	5.0	15.0	7.0	720
GS-6	2.5	20.0	1.8	410
GS-7	2.5	21.0	0.50	900
GS-8	2.5	19.5 <sup>1</sup>	1.0	5,600
	5.0	19.2 <sup>1</sup>	1.8	8,800
GS-9	2.5	4.0 <sup>1</sup>	13.5	> 20,000
	5.0	0.80 <sup>1</sup>	19.5	> 20,000
GS-10	2.5	13.5 <sup>1</sup>	6.8	> 20,000
	5.0	0.80 <sup>1</sup>	17.0	> 20,000
GS-11	2.5	16.0 <sup>1</sup>	4.3	> 20,000

<sup>1</sup> Pressure reading on sampling pump was high. Measured oxygen concentration may not be representative of actual soil gas oxygen concentrations. Actual oxygen concentration is likely to be lower.



### 2.1.3 Vent Well, Monitoring Point, and Thermocouple Installation

On October 3, 1992, one vent well (VW) and three monitoring points (MPs) were installed, and soil samples were collected for analyses. The monitoring points were labeled as follows: H1-MPA; H1-MPB; and H1-MPC. The locations of the vent well and monitoring points are shown in Figure 2. A cross section of the vent well and monitoring points showing site lithology and construction detail is shown in Figure 4.

The vent well was installed at a depth of 7.0 feet into an 8-inch-diameter borehole. The vent well consisted of Schedule 40 2-inch-diameter polyvinyl chloride (PVC) piping with 3.0 feet of ten-slot screen. The annular space corresponding to the screened area of the well was filled with silica sand, and the annular space above the screened interval was filled with bentonite to prevent short-circuiting of air to or from the surface.

Soil gas probes consisted of 1/4-inch tubing with a 1-inch-diameter, 6-inch screened area. The annular space corresponding to the screened area was filled with silica sand, whereas the interval between the screened areas was filled with bentonite, as was the annular space from the shallowest monitoring point to the ground surface. The monitoring points were installed at depths as follows:

- Monitoring point H1-MPA was installed at a depth of 5.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to two depths: 2.5 and 5.0 feet.
- Monitoring point H1-MPB was installed at a depth of 5.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to two depths: 2.5 and 5.0 feet.
- Monitoring point H1-MPC was installed at a depth of 6.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to two depths: 3.5 and 6.0 feet.

A Type K thermocouple was installed with monitoring points H1-MPA-2.5' and H1-MPA-5.0'.




Figure 4. Cross Section of Vent Well and Monitoring Points at Building 1639 Showing Site Lithology and Construction Detail (not to scale)

#### **2.1.4 Soil and Soil Gas Sampling and Analyses**

Split-spoon soil samples were collected at depths of 4.0 to 4.5 feet and 4.5 to 5.0 feet from the vent well borehole and were labeled H1-VW-4'-4.5' and H1-VW-4.5'-5.0', respectively. A soil sample also was collected from monitoring point A at a depth of 3.0 to 4.0 feet and was labeled H1-A-3'-4'. The samples were sent under chain of custody to Engineering-Science Inc., Berkeley Laboratory for analysis of benzene, toluene, ethylbenzene, and xylenes (BTEX); TPH; alkalinity; moisture content; pH; iron; total phosphorous; total Kjeldahl nitrogen; and particle size analysis.

Soil vapor samples were collected from all monitoring points and were labeled H1-A-2.5, H1-A-5, H1-B-2.5, H1-B-5, H1-C-3.5, and H1-C-6. These samples were sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analysis of BTEX and TPH.

#### **2.1.5 Soil Gas Permeability and Radius of Influence**

A detailed description of the method for conducting a soil gas permeability test, including equations to compute  $k$ , the soil gas permeability, is given in the Test Plan and Technical Protocol (Hinchee et al., 1992).

Prior to air injection, the monitoring points were allowed to set up for 24 hours. Air was injected with a portable 1-horsepower (HP) explosion-proof positive displacement blower unit. After air injection was initiated, pressure readings were taken approximately every 1 to 2 minutes for the first hour, then approximately every 10 minutes for the following hour. The Hyperventilate™ computer model was used to calculate the soil gas permeability.

#### **2.1.6 In Situ Respiration Test**

Immediately following the soil gas permeability test, air containing approximately 1% helium was injected into the soil for approximately 24 hours, beginning on October 6. Air was injected concurrently into the background monitoring well to measure the natural biodegradation of organic material in the soil. The setup for the in situ respiration test is described in the Test Plan and Technical Protocol (Hinchee et al., 1992). The pump used for air injection was a 1/3-HP diaphragm pump. Air and helium were injected through the following monitoring points at the depths indicated: H1-MPA-5.0'; H1-MPB-2.5'; H1-MPB-5.0'; and H1-MPC-6.0'. After the air/helium injection was

turned off, the respiration gases were monitored periodically. The respiration test was terminated on October 10.

Helium concentrations were measured during the in situ respiration test to quantify helium leakage to or from the surface around the monitoring points. Helium loss over time is attributed to either diffusion or leakage. A rapid drop in helium concentration followed by a leveling is an indication of leakage. A gradual loss along with an apparent first-order curve is an indicator of diffusion. As a rough estimate, the diffusion of gas molecules is inversely proportional to the square root of the molecular weight of the gas. Based on molecular weights of 4 for helium and 32 for oxygen, helium gas diffuses about 2.8 times faster than oxygen, or the diffusion of oxygen is 0.35 times the rate of helium diffusion. As a general rule, we have found that if helium concentrations are at least 50 to 60% of the initial levels at test completion, measured oxygen uptake rates are representative. Greater helium loss indicates a problem, and oxygen utilization rates are not considered representative.

To compare data from one site to another, a stoichiometric relationship of the oxidation of the hydrocarbon was assumed. Hexane was used as the representative hydrocarbon for the organic contaminant. The stoichiometric relationship is given by:



Based on the utilization rates (% per day), the biodegradation rates in terms of milligrams as a hexane equivalent per kilogram of soil per day were computed using the equation below by assuming a soil porosity of 0.2 and a bulk density of 1,440 kg/m<sup>3</sup>.

$$K_b = \frac{-K_o A D_o C}{100} \quad (2)$$

where:  $K_b$  = biodegradation rate (mg/kg/day)

$K_o$  = oxygen utilization rate (percent per day)

$A$  = volume of air/kg of soil, in this case  $300/1,440 = 0.21$

$D_o$  = density of oxygen gas (mg/L) assumed to be 1,330 mg/L

C = mass ratio of hydrocarbon to oxygen required for mineralization, assumed to be 1/3.5 from the above stoichiometric equation.

## 2.2 Results and Discussion

### 2.2.1 Soil and Soil Gas Analyses

Results of the soil analyses for BTEX and TPH at Building 1639 are presented in Table 2. The analytical report for this site is presented in Appendix B. Concentrations of the BTEX compounds in soil samples ranged from 0.015 mg/kg (ethylbenzene) up to 12 mg/kg (total xylenes), whereas TPH concentrations ranged from below the detection limit ( $<0.0040$  mg/kg) to 22 mg/kg. The soil vapor analyses also showed similar measurements of BTEX and TPH, with concentrations of TPH ranging from 280 ppmv to 19,000 ppmv and from 0.11 ppmv (ethylbenzene) up to 67 ppmv (total xylenes) of the BTEX compounds (Table 2). The results of the soil chemistry analyses are summarized in Table 3.

### 2.2.2 Soil Gas Permeability and Radius of Influence

The raw data for the soil gas permeability test at Building 1639 are presented in Appendix C. Using the Hyperventilate™ computer model, soil gas permeabilities were calculated at each of the monitoring points. These data are presented in Table 4. The soil gas permeability varied considerably, with values ranging from 24 darcy up to  $5.4 \times 10^8$  darcy. Typically, the radius of influence is calculated by plotting the log of the pressure change at a specific monitoring point versus the distance from the vent well. The radius of influence would then be the distance where 1 inch of water pressure can be measured. However, in this instance, 1 inch of water pressure was not achieved at any monitoring point (Figure 5); therefore, a radius of influence based on these specifications cannot be definitively determined at this site, other than to say it is less than 8.7 feet.

### 2.2.3 In Situ Respiration Test

The results of the in situ respiration test for Building 1639 are presented in Appendix D. Each figure in Appendix D illustrates the oxygen, carbon dioxide, and helium concentrations as a

Table 2. Results From Soil and Soil Gas Analyses for BTEX and TPH at Building 1639

Matrix	Sample Name	Benzene (mg/kg)	Toluene (mg/kg)	Ethylbenzene (mg/kg)	Total Xylenes (mg/kg)	TPH <sup>1</sup> (mg/kg)
Soil	H1-VW-4'-4.5'	0.048	0.020	0.015	0.020	22
	H1-VW-4.5'-5.0'	0.67	0.27	0.43	0.45	15
	H1-A-3'-4'	1.0	4.3	1.3	12	<0.0040
Matrix	Sample Name	Benzene (ppmv)	Toluene (ppmv)	Ethylbenzene (ppmv)	Total Xylenes (ppmv)	TPH <sup>2</sup> (ppmv)
Soil Gas	H1-A-2.5	5.2	4.2	1.1	2.9	5,600
	H1-A-5	27	35	10	30	19,000
	H1-B-2.5	2.8	1.3	0.84	1.9	2,700
	H1-B-5	2.4	0.84	0.42	1.5	3,200
	H1-C-3.5	0.44	0.13	0.11	0.37	280
	H1-C-6	11	20	9.3	67	11,000

<sup>1</sup> Referenced to a reference oil composed of a mixture of 2,2,4-trimethylpentane, *n*-hexadecane, and chlorobenzene.

<sup>2</sup> TPH referenced to jet fuel (molecular weight = 156).

**Table 3. Results From Soil Chemistry Analyses at Building 1639**

Parameter	Sample Name		
	H1-VW-4'-4.5'	H1-VW-4.5'-5.0'	H1-A-3'-4'
Alkalinity (mg/kg CaCO <sub>3</sub> )	< 50	< 50	< 50
Moisture (% by weight)	22.2	21.8	5.8
pH	5.8	6.0	6.1
Iron (mg/kg)	7,980	6,260	8,630
Total Phosphorous (mg/kg)	370	290	300
Total Kjeldahl Nitrogen (mg/kg)	1,100	730	70
Particle Size Analysis (%)	Gravel: 11.5	Gravel: 0.5	Gravel: 26
	Sand: 59	Sand: 72	Sand: 55
	Silt: 27	Silt: 23	Silt: 16
	Clay: 6	Clay: 4.5	Clay: 3

**Table 4. Results of Hyperventilate™ Soil Gas Permeability Analysis at Building 1639**

Monitoring Point	Depth (ft)	Soil Gas Permeability (darcy)
H1-MPA	2.5	24
	5.0	130
H1-MPB	2.5	1,400
	5.0	6,200
H1-MPC	3.5	5.4 x 10 <sup>8</sup>
	6.0	28




Figure 5. Radius of Influence at Building 1639



function of time. An example of typical oxygen utilization at this site is shown in Figure 6, where oxygen utilization and carbon dioxide production at monitoring point H1-MPA-5.0' is illustrated. A summary of the oxygen utilization and carbon dioxide production rates and corresponding biodegradation rates is shown in Table 5. The biodegradation rates measured at this site were fairly high, with rates ranging from 8.0 mg/kg/day to 27 mg/kg/day based on oxygen utilization, and from 0.48 mg/kg/day to 4.3 mg/kg/day based on carbon dioxide production.

Loss of helium was insignificant at all monitoring points, indicating that the monitoring points were well sealed and that the oxygen depletion observed was a result of biodegradation.

Soil temperatures were measured during the in situ respiration test. Temperatures during the test ranged from 17.9 to 19.3°C at monitoring point H1-MPA-2.5' and from 18.7 to 20.7°C at monitoring point H1-MPA-5.0'.

#### 2.2.4 Bioventing Demonstration

The decision was made to install a bioventing system at Building 1639. A 1-HP blower was installed at the site on October 14, 1992. Air injection was initiated on October 14 at a flowrate of 2.5 scfm.

**Table 5. Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at Building 1639**

Monitoring Point	Oxygen Utilization Rate (%/hour)	Biodegradation Rate (mg/kg/day)	Carbon Dioxide Production Rate (%/hour)	Biodegradation Rate (mg/kg/day)
Background	0.0073	0.14	0.0087	0.19
H1-MPA-5.0'	1.4	27	0.076	1.6
H1-MPB-2.5'	0.42	8.0	0.034	0.74
H1-MPB-5.0'	0.58	11	0.022	0.48
H1-MPC-6.0'	0.69	13	0.20	4.3




Figure 6. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point H1-MPB-5.0'

### 3.0 BUILDING 1812

#### 3.1 Chronology of Events and Site Activities

Although oxygen levels measured during the soil gas survey indicated that some areas at the Building 1812 site may be limited, oxygen concentrations measured at the permanent monitoring points were fairly high. Therefore, an in situ respiration test was not conducted at this site. However, because measurements taken during the soil gas survey indicated that some areas were oxygen-limited, a bioventing system was installed at the site in order to treat those areas. Other activities were conducted at the site according to the Test Plan and Technical Protocol (Hinchee et al., 1992).

##### 3.1.1 Groundwater Measurements

Groundwater depth was measured at one monitoring well (HB-02) at Building 1812. The groundwater level was measured on October 1, 1992 and was recorded at 3.98 feet.

##### 3.1.2 Soil Gas Survey

On October 1, 1992, a limited soil gas survey was conducted to locate a suitable test area at Building 1812. Soil gases were sampled by driving a 5/8-inch-diameter stainless steel probe into the soil with a hammer drill. Soil gas was withdrawn with a vacuum pump and analyzed for oxygen, carbon dioxide, and TPH. Soil gas measurements were taken as described in Section 2.1.2.

The soil gas probes were driven to depths ranging from 2.0 to 5.0 feet at several locations at Building 1812. Table 6 provides the initial concentrations of oxygen, carbon dioxide, and TPH for the various locations at Building 1812. Relatively high concentrations of oxygen were found at most of the soil gas probes, with concentrations ranging from 3 to 20%. Relatively low concentrations of carbon dioxide (0.05 to 8.5%) and TPH (10 ppm to 800 ppm) were encountered. The oxygen concentrations in the soil gas indicate that some areas at this site are oxygen-limited and may respond to bioventing.

Table 6. Initial Soil Gas Composition at Building 1812

Monitoring Point	Depth (ft)	Oxygen (%)	Carbon Dioxide (%)	TPH (ppm)
GS-1	2.5	19.5	0.7	120
GS-2	2.5	20	0.05	10
	5.0	NS	NS	NS
GS-3	2.25	20.2	0.60	87
GS-4	2.5	17	0.30	40
	4.0	19.8 <sup>1</sup>	0.08	20
GS-5	2.5	15	3.8	220
	5.0	13	5.1	270
GS-6	2.5	16.5	1.3	120
	5.0	NS	NS	NS
GS-7	2.0	9.1	6.0	440
	3.5 - 4.0	7.0	7.2	480
GS-8	2.5	17.5	1.2	250
GS-9	2.0	17	1.4	280
GS-10	2.0	3.0	8.5	800
GS-11	2.0	18.8	0.40	180
	3.0	18.3	0.60	96
	4.0	18.9 <sup>1</sup>	2.7	220
GS-12	2.0	17	0.10	41
	3.0	18	0.70	120
	4.0	17.5	0.10	50

NS Not sampled. Groundwater was encountered at this depth.

<sup>1</sup> Pressure reading on sampling pump was high. Measured oxygen concentration may not be representative of actual soil gas oxygen concentrations. The actual oxygen concentration is likely to be lower.

### 3.1.3 Vent Well, Monitoring Point, and Thermocouple Installation

On October 4, 1992, one vent well and three monitoring points were installed, and soil samples were collected for analyses. The monitoring points were labeled H2-MPA, H2-MPB, and H2-MPC. The locations of the vent well and monitoring points are shown in Figure 3. A cross section of the vent well and monitoring points showing site lithology and construction detail is shown in Figure 7.

The vent well was installed at a depth of 7.0 feet into an 8-inch-diameter borehole. The vent well consisted of Schedule 40 2-inch-diameter PVC piping with 3.6 feet of ten-slot screen. The annular space corresponding to the screened area of the well was filled with silica sand, whereas the annular space above the screened interval was filled with bentonite to prevent short-circuiting of air to or from the surface.

Soil gas probes consisted of 1/4-inch tubing with a 1-inch-diameter, 6-inch screened area. The annular space corresponding to the screened area was filled with silica sand, whereas the interval between the screened areas was filled with bentonite, as was the annular space from the shallowest monitoring point to the ground surface. The monitoring points were installed at depths as follows:

- Monitoring point H2-MPA was installed at a depth of 5.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to two depths: 2.5 and 5.0 feet.
- Monitoring point H2-MPB was installed at a depth of 7.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to three depths: 2.5, 5.0, and 7.0 feet.
- Monitoring point H2-MPC was installed at a depth of 6.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to three depths: 2.5, 4.5, and 6.0 feet.

A Type K thermocouple was installed with monitoring points H2-MPA-2.5' and H2-MPA-5.0'.




Figure 7. Cross Section of Vent Well and Monitoring Points at Building 1812 Showing Site Lithology and Construction Detail (not to scale)

### **3.1.4 Soil and Soil Gas Sampling and Analyses**

Split-spoon soil samples were collected at depths of 3.0 to 3.5 feet and 4.0 to 4.5 feet from the vent well borehole and were labeled H2-VW-3'-3.5' and H2-VW-4'-4.5', respectively. The samples were sent under chain of custody to Engineering-Science Inc., Berkeley Laboratory for analyses of BTEX; TPH; alkalinity; moisture content; pH; iron; total phosphorous; total Kjeldahl nitrogen; and particle size analysis.

### **3.1.5 Soil Gas Permeability and Radius of Influence**

A detailed description of the method for conducting a soil gas permeability test, including equations to compute  $k$ , the soil gas permeability, is given in the Test Plan and Technical Protocol (Hinchee et al., 1992).

Prior to air injection, the monitoring points were allowed to set up for 24 hours. A portable 1-HP explosion-proof positive displacement blower unit was used to inject air. After air injection was initiated, pressure readings were taken approximately every 1 to 2 minutes for the first hour, then approximately every 10 minutes for the following hour. The Hyperventilate™ computer model was used to calculate the soil gas permeability.

## **3.2 Results and Discussion**

### **3.2.1 Soil and Soil Gas Analyses**

Results of the soil analyses for BTEX and TPH are presented in Table 7. The analytical report for this site is presented in Appendix B. All of the BTEX compounds were at concentrations below the detection limit in sample H1-VW-3'-3.5' and only small quantities of toluene (0.015 mg/kg) and total xylenes (0.051 mg/kg) were detected in sample H1-VW-4'-4.5'. TPH concentrations were low in sample H1-VW-3'-3.5' (12 mg/kg); however, 13,000 mg/kg of TPH was detected in sample H1-VW-4'-4.5'. The results of the soil chemistry analyses are summarized in Table 8.

Table 7. Results From Soil Analyses for BTEX and TPH at Building 1812

Sample Name	Benzene (mg/kg)	Toluene (mg/kg)	Ethylbenzene (mg/kg)	Total Xylenes (mg/kg)	TPH <sup>1</sup> (mg/kg)
H2-VW-3'-3.5'	<0.062	<0.072	<0.052	<0.093	12
H2-VW-4'-4.5'	<0.0032	0.015	<0.0026	0.051	13,000

<sup>1</sup> Referenced to a reference oil composed of a mixture of 2,2,4-trimethylpentane, *n*-hexadecane, and chlorobenzene.

Table 8. Results From Soil Chemistry Analysis at Building 1812

Parameter	Sample Name	
	H2-VW-3'-3.5'	H2-VW-4'-4.5'
Alkalinity (mg/kg CaCO <sub>3</sub> )	90	< 50
Moisture (% by weight)	3.2	6.1
pH	7.0	6.2
Iron (mg/kg)	8,160	5,460
Total Phosphorous (mg/kg)	450	600
Total Kjeldahl Nitrogen (mg/kg)	66	53
Particle Size Analysis (%)	Gravel: 10	Gravel: 1.0
	Sand: 69.5	Sand: 76
	Silt: 19	Silt: 21.5
	Clay: 1.5	Clay: 1.5



### 3.2.2 Soil Gas Permeability and Radius of Influence

The raw data for the soil gas permeability test at Building 1812 are presented in Appendix E. Using the Hyperventilate™ computer model, soil gas permeabilities were calculated at each of the monitoring points. These data are presented in Table 9. The soil gas permeability varied considerably, with values ranging from 2.5 darcy up to  $6.3 \times 10^9$  darcy. The radius of influence where 1 inch of water could be measured was calculated by plotting the log of the pressure change at the monitoring points versus the distance from the vent well (Figure 8). If pressure changes at all monitoring points are included, no radius of influence can be calculated based on these specifications. However, if the pressure change at monitoring points below the water table are not included (H2-MPA-5.0' and H2-MPB-5.0'), the radius of influence at Building 1812 is estimated to be approximately 7.5 feet.

### 3.2.3 Bioventing Demonstration

The decision was made to install a bioventing system at Building 1812. A 1-HP blower was installed on October 14, 1992. Air injection was initiated on October 14 at a flowrate of 4.25 scfm.

## 4.0 BACKGROUND AREA ACTIVITIES

The background area was located as shown in Figure 1. An existing monitoring well was used as the vent well and was screened from 1.5 feet to 9.0 feet. Soil samples were taken 2 feet from the monitoring well by hand auger. Site lithology at this area was representative of that in the contaminated areas.

A split-spoon soil sample was collected at a depth of 2.5 to 3.0 feet from the vent well borehole and was labeled H1-BKG-2.5'-3'. A soil vapor sample also was collected from the vent well after installation and labelled H1-BG-1.5-9. The soil samples were sent under chain of custody to Engineering-Science Inc., Berkeley Laboratory for analysis of BTEX; TPH; alkalinity; moisture content; pH; iron; total phosphorous; total Kjeldahl nitrogen; and particle size analysis. The soil vapor sample was sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analysis of BTEX and TPH.

**Table 9. Results of Hyperventilate™ Soil Gas Permeability Analysis**

<b>Monitoring Point</b>	<b>Depth (ft)</b>	<b>Soil Gas Permeability (darcy)</b>
H2-MPA	2.5	$6.3 \times 10^9$
	5.0	2.5
H2-MPB	2.5	$3.1 \times 10^9$
	5.0	430
	7.0	ND
H2-MPC	2.5	NR
	4.5	NR
	6.0	NR

ND No data were collected from this monitoring point.

NR No pressure readings were detected at this monitoring point.




Figure 8. Radius of Influence at Building 1812

Results of the soil and soil vapor analyses for BTEX and TPH are presented in Table 10. The analytical report for the background area is presented in Appendix B. All of the BTEX compounds were at concentrations below the detection limit in the soil sample, and only a small quantity of TPH (84 mg/kg) was detected. The soil vapor sample contained higher concentrations of BTEX compounds with concentrations ranging from 0.16 ppmv (benzene) up to 4.7 ppmv (total xylenes). The results of the soil chemistry analyses also are summarized in Table 10.

An in situ respiration test was conducted at the background area beginning on October 9 after 24 hours of air injection. The test was concluded on October 11. Very little decrease in oxygen concentration occurred during the course of the in situ respiration test (Figure 9).

## 5.0 FUTURE WORK

Base personnel will be required to perform a simple weekly system check to ensure that the blower is operating within its intended flowrate, pressure, and temperature range. An on-site briefing for base personnel who will be responsible for blower system checks was conducted when the blowers were installed. The principle of operation was explained, and a simple checklist and logbook were provided for blower data. Base personnel will be asked to perform minor maintenance activities, such as replacing filters or gauges, or draining condensate from knockout chambers, but they will not be expected to perform complicated repairs or analyze gas samples. Replacement filters and gauges will be provided and shipped to the base, and serious problems, such as motor or blower failures, will be corrected by Battelle.

The progress of this system will be monitored by conducting semiannual respiration tests in the vent well and in each monitoring point and by regularly measuring the oxygen, carbon dioxide, and hydrocarbon concentrations in the extracted soil gas and comparing them to background levels. At least twice each year, the progress of the bioventing test will be reported to the base point-of-contact.

Table 10. Results From Soil Chemistry Analysis at Background Area

Parameter	Sample Name	
	Soil Sample H1-BKG-2.5'-3'	Soil Vapor Sample H1-BG-1.5-9
Benzene	< 0.00060 mg/kg	0.16 ppmv
Toluene	< 0.00070 mg/kg	0.93 ppmv
Ethylbenzene	< 0.00050 mg/kg	0.43 ppmv
Total Xylenes	< 0.00090 mg/kg	4.7 ppmv
TPH	84 mg/kg	340 ppmv
Alkalinity (mg/kg CaCO <sub>3</sub> )	< 50	
Moisture (% by weight)	9.8	
pH	6.6	
Iron (mg/kg)	11,600	
Total Phosphorous (mg/kg)	460	
Total Kjeldahl Nitrogen (mg/kg)	91	
Particle Size Analysis (%)	Gravel: 11.5	
	Sand: 48	
	Silt: 32	
	Clay: 8.5	




Figure 9. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at the Background Area

## 6.0 REFERENCE

Hinchee, R.E., S.K. Ong, R.N. Miller, D.C. Downey, and R. Frandt. 1992. *Test Plan and Technical Protocol for a Field Treatability Test for Bioventing* (Rev. 2), Report prepared by Battelle Columbus Operations, U.S. Air Force Center for Environmental Excellence, and Engineering Sciences, Inc. for the U.S. Air Force Center for Environmental Excellence, Brooks Air Force Base, Texas.

**APPENDIX A**

**TEST PLAN FOR HANSCOM AFB, MASSACHUSETTS**





505 King Avenue  
Columbus, Ohio 43201-2693  
Telephone (614) 424-6424  
Facsimile (614) 424-5263

September 2, 1992

Captain Catherine Vogel  
Department of the Air Force  
Building 1117  
HQ AFESC/RDVW  
Tyndall AFB, Florida 32403-6001

Dear Cathy:

**SUBJECT: TEST PLAN FOR BIOVENTING INITIATIVE FIELD TEST  
AT BUILDING 1639 AND BUILDING 1812, HANSCOM AFB, MA.**

This letter was prepared to accompany the report titled "Test Plan and Technical Protocol for a Field Treatability Test for Bioventing." The report was developed as a generic test plan for the Air Force Bioventing Initiative Project in which Hanscom AFB is participating. This letter outlines site specific information to support the generic test plan.

The sites chosen for the bioventing test initiative are Building 1639 and Building 1812. Building 1639 is the base fuel service station (see map Figure 1). There have been three reported petroleum releases (gasoline, #2 fuel oil, and waste lubricating oil) at this facility since November 1990. The site at Building 1812 is the location of a heating oil fuel tank (see Figure 2). The tank was replaced recently and soil TPH concentrations as high as 2830 mg/Kg have been reported.

The purpose of this project is to investigate the feasibility of using the bioventing technology to remediate petroleum contaminated soils at the above mentioned sites.

**Site Description:**

Hanscom AFB is located in Bedford, Massachusetts. A generalized geologic and hydrogeologic column is shown in Figure 3. Groundwater at Hanscom is encountered at 3-8 feet. Figures 4 and 5 show test boring logs for two soil borings in the vicinity of the bioventing initiative sites.

Soil contamination at Building 1639 ranges from 599 ppm to 4400 ppm TPH. Soil samples at Building 1812 have indicated TPH concentrations as high as 2800 ppm. Boring and depth locations for these samples were not immediately available. Locations for initiating the soil gas survey at each site will be determined with direction from the Base POC.

### Project Activities-

The following field activities are planned for the bioventing project at Hanscom AFB. The same procedures will be followed at each site. Additional detail can be found in Section 5.0 of the test plan and technical protocol.

- 1- A small scale soil gas survey will be conducted to identify an appropriate location for installation of the bioventing system. The soil gas survey will be conducted in areas which site data have shown to be the most contaminated. Soil vapor from the candidate site should exhibit high petroleum hydrocarbon concentrations (10,000 ppm or greater), relatively low O<sub>2</sub> concentrations (0 % to 2.0 %), and relatively high CO<sub>2</sub> concentrations (depending on soil type, 2.0 % to 10.0 %, or higher). An uncontaminated background location will also be identified.
- 2- Once the installation sites are located one vent well and three 3-level soil gas monitoring points will be installed in the contaminated location and one vent well will be installed in a background area (one background area will be used for both test sites, if possible). The wells and monitoring points will be installed using a two-man power auger or a portable drill rig to bore down to just above the water table. Three to four soil samples will be collected for chemical/physical analysis.
- 3- The air permeability test will be conducted in the contaminated test location.
- 4- Following the air permeability test, in situ respiration tests will be conducted in both the contaminated and the background test locations.
- 5- Depending on the results of the air permeability test and the in situ respiration test, a decision will be made whether or not to install a blower system in the contaminated area for the long term bioventing test. If the decision is made to install the system, the blower will be plumbed to the vent well and bioventing will be started (assuming power is available). Site personnel will be trained for blower operation prior to Battelle leaving the site.
- 6- A report detailing the results of the in situ respiration test and the air permeability test will be provided to the project officer and the base POC.

### Schedule-

Field activities at Hanscom AFB are planned to begin on September 28, 1992. Battelle will have 2 to 3 people on site for approximately 3 weeks.

**Base Support-**

Hanscom AFB needs to be able to provide the following:

- Digging permits and utility clearance need to be obtained prior to the initiation of the field work. Underground utilities should be clearly marked to reduce the chance of utility damage or personal injury during soil gas probe and well installation. Battelle will not be able to begin field operations without these clearances.
- Electrical power will need to be easily accessible from the project site. The air permeability test and in situ respiration test can be performed using a gasoline powered electric generator. The operation of the bioventing system will require a permanent 220/110 V power source. If power will not be available immediately after the test is completed the bioventing system will be installed for start-up at a later date.
- The Air Force will need to provide drums to contain soil cuttings and provide for contaminated soil disposal.
- Base and site clearance will be required for Battelle's site employees. We will furnish you with personal information for each person at least one week prior to starting field operations.
- Regulatory approval, if any is required, will need to be obtained by the base prior to start-up of the bioventing system. The system will likely be configured for air injection so there will be no point source vapor emission from the system. The wells to be installed will not intersect the apparent water table and no groundwater will be pumped. A letter from the Massachusetts DEP (Attachment 1) presented several concerns with the bioventing test plan. These concerns are addressed below.

**Regulatory Issues-**

- 1- **General Approval Requirements-** DEP approval is necessary for the initiation of remediation of petroleum releases. This approval should be pursued by the base for the long-term bioventing test. The soil gas survey, vent well and monitoring point installation, air permeability test, and in situ respiration test are all standard field activities that generally do not require any regulatory approval prior to initiation. Battelle is available to discuss any of these activities with the DEP prior to start up of field activities.
- 2- **Air Quality Permits and Approvals-** The only air injection planned for this study is the injection of ambient atmospheric air into the vadose zone as a oxygen source for biological activity. Should conditions require the extraction of soil gas (i.e. a basement adjacent to the vent well) then treatment and permitting requirements will be discussed with the DEP.

Captain Catherine Vogel  
Department of the Air Force  
September 2, 1992  
Page 4

- 3- **Groundwater Remediation-** The purpose of this research project is to investigate the efficacy of bioventing for the remediation of petroleum contaminated soils in the vadose zone. While bioventing, as configured for this project, does not directly address groundwater contamination, it has proven to be an effective technology for the remediation of petroleum contaminated soils. These soils typically act as the long-term source of localized groundwater contamination. Removal of the contaminant source is paramount in any groundwater remediation effort.
- 4- **Nutrient Addition-** Nutrient addition is not currently planned for this site.
- 5- **Field Screening of Split-Spoon Samples-** The Jar Headspace Technique will be employed for selected samples. Samples will be analyzed for BTEX via EPA Method 8020 and TPH via EPA Method 418.1. Samples will also be analyzed for nutrients.

Please let me know if there are any other regulatory concerns which need to be addressed. If you have any questions please feel free to call me at (614) 424-6122.

Sincerely,

Jeffrey A. Kittel  
Researcher  
Environmental Technology

JAK:mla

ATTACHMENT 1



Commonwealth of Massachusetts

Executive Office of Environmental Affairs

**Department of  
Environmental Protection**

Metro Boston/Northeast Regional Office

William F. Weld  
GovernorDaniel S. Greenbaum  
Commissioner

JUN 10 1992

Mr. Robert Spelfogel  
Hanscom Air Force Base  
3245th ABG/DEEV  
Bedford, MA 01730

RE: BEDFORD - Hanscom AFB  
Bioventing Treatability Test  
DEP Case #3-3882

Dear Mr. Spelfogel:

The Department of Environmental Protection is in receipt of a January 1992 "Report, Test Plan And Technical Protocol For A Field Treatability Test For Bioventing". This report was prepared for the U.S. Air Force by Battelle Corporation and was submitted to the Department by the Air Force with a request to provide information concerning the regulatory requirements of the bioventing remediation technique. Preliminary approval of the bioventing concept was also requested. Hanscom Air Force Base is planning to contract Battelle Corporation to conduct Bioventing Treatability Testing at Buildings 1812 and 1639.

Building 1639 (DEP Case #3-3882) is the Air Force Base Service Station. Department files indicate three petroleum release incidents at this location. These releases were assigned the incident response numbers N92-0837, N91-794 and N90-1884. Gasoline, #2 fuel oil, and waste lubricating oil have been released to soil and/or groundwater at this site.

At Building 1812 soil samples collected from borings were found to be contaminated with concentrations of Total Petroleum Hydrocarbons as high as 2830 mg/kg.

The bioventing process uses aeration of subsurface soils to stimulate in-situ biological activity and promote bioremediation. The following points outline the bioventing process.

Hanscom AFB  
Page 2

- (1) Forced air is supplied to the contaminated unsaturated zone to produce the aerobic conditions necessary for biodegradation.
- (2) Airflow is optimized to reduce volatilization while maintaining aerobic conditions.
- (3) Local soil gas conditions are monitored to assure aerobic conditions.
- (4) Moisture and nutrients are added to the contaminated unsaturated zone if necessary.
- (5) Dewatering is conducted, if necessary to lower the water table below the contaminated soils.

After review of the above mentioned report the Department hereby approves of the initiation of Bioventing Field Treatability Testing at Buildings 1639 and 1812. The following comments are also provided:

\* General Approval Requirements.

Departmental approval must be obtained for the initiation of the remediation of releases of petroleum or hazardous materials at Locations To Be Investigated or Confirmed Disposal Sites. A bioventing system to remediate petroleum or hazardous materials releases at Hanscom Air Force Base is subject to the above-mentioned approvals.

\* Air Quality Permits and Approvals.

Page 5 Section 2.1.3 states that when air is injected into a contaminated zone and withdrawn from clean soils volatile hydrocarbons are allowed to degrade prior to being withdrawn thereby eliminating contaminated off-gases. "This configuration typically does not require air emission permitting".

Be advised that all air emissions resulting from treatment systems at petroleum or hazardous materials disposal sites are subject to the Air Pollution Control Regulations at 310 CMR 6.00-8.00 in addition to the requirements of the Massachusetts Contingency Plan at 310 CMR 40.000.

Hanscom AFB  
Page 3

In general, if an air contaminant source emits less than one ton of contaminants per year, then that emission source is not subject to application for approval from the Department of Environmental Protection's Division of Air Quality.

Whether or not the emission source emits more than one ton of pollutants per year, if the emission is part of a system being operated to remediate a release of petroleum or hazardous materials to the environment, then that system is subject to M.G.L. c.21E and the MCP. The DEP Bureau Of Waste Site Cleanup requires that off-gas controls be installed on all point source remedial air emissions where Soil Vapor Extraction systems are utilized. Off-gas controls must be implemented during the first 180 days of operation at a minimum. Off-gas treatment must reduce vapor-phase emissions of VOC's by at least 95 percent. Approval to operate without emission controls after the first 180 days are contingent upon receipt of information confirming the absence of a threat of harm to human health or the environment.

\* Page 5 indicates that during a 1988 study at Hill Air Force Base it became apparent that bioventing had great potential for remediating JP-4 fuel-contaminated soils.

It is not clear however that bioventing is effective for remediation of groundwater contaminated with fuel oils. Many of the components contained in aircraft fuels, diesel fuel and heavier petroleum fuel products are not significantly volatile and would not readily be transferred from the groundwater to the unsaturated zone where they could be treated by the bioventing system. In order to achieve a permanent solution to the petroleum contamination present at a site it may be necessary to reduce the levels of contaminants in soil and groundwater to levels which do not pose a significant or otherwise unacceptable risk to public health, safety, public welfare or the environment.

\* Page 6 indicates that adding nutrients as required to increase biodegradation rates may be necessary. The addition of nutrients to the subsurface is subject to the requirements of M.G.L. c.21 and the Groundwater Discharge Permit Regulations (314 CMR 5.00). Nutrient addition may be initiated only upon receipt of a Groundwater Discharge Permit issued by the DEP Division of Groundwater Pollution Control.



Hanscom AFB  
Page 4

\* Page 42, Section 2.1.2 - Exploratory Boring in Deep Soils, states that "Split-spoon samples will be visually checked for fuel contamination and screened for volatile emissions by passing a hydrocarbon analyzer slowly over the open split-spoon".


This method is not acceptable for the field screening of split spoon samples for petroleum hydrocarbon contamination. The Jar Headspace Technique (Reference: "Management Procedures for Excavated Soils Contaminated with Virgin Petroleum Oils", Policy #WSC-89-001) should be applied for the measurement of volatile petroleum constituents. Total Petroleum Hydrocarbons by Infrared (Standard Methods 503 or 5520) or Oil Fingerprinting (ASTM D 3328) should be used to determine concentrations of non-volatile petroleum hydrocarbons.

If you have any questions regarding this matter please do not hesitate to contact Jack Miano at the letterhead address or telephone (617) 935-2160 X142.

Very truly yours,



Jack Miano  
Environmental Engineer



Stephen M. Johnson  
Acting Chief,  
Site Management Branch

SMJ/JM/ae

cc: DEP, BWSC, Boston, Attn: Jeff Krukonis  
DEP, DWS, NERO, Attn: Jim Persky  
Bedford BOH, Attn: David Black  
Bedford DPW, 312 Great Rd., Bedford, MA 01730,  
Attn: Mr. Richard Warrington, Director




FIGURE 1. SITE DIAGRAM FOR BUILDING 1639

DELETED AIR FORCE BASE  
FORMER LOCATION OF UNDERGROUND STORAGE TANK  
BUILDING NO. 1816

HANSCOM AIR FORCE BASE, MASSACHUSETTS




FIGURE 2. SITE DIAGRAM FOR BUILDING 1812

**GENERALIZED GEOLOGIC AND HYDROGEOLOGIC COLUMN**  
**INVESTIGATION OF SUSPECTED HAZARDOUS WASTE SITES**  
**HANSCOM AIR FORCE BASE, MASSACHUSETTS**












PERIOD	EPOCH	FORMATION	COLUMNAR SECTION	APPROXIMATE THICKNESS (11)	CHARACTER	
QUATERNARY	RECENT	FILL		0-10	TOPSOIL & CLEAN SANDY FILL	
	PLEISTOCENE (WISCONSIN)	? unconformable				
		PEAT		0-7	BLACK ORGANIC SANDS & PEAT	
		? unconformable				
		OUTWASH DEPOSITS		0-18	Clean Coarse to fine Sands SATURATED, PERMEABLE	UPPER AQUIFER
		LACUSTRINE DEPOSITS		0-65	Fine SANDS & SILTS Grading to clayey Silts, Low permeability, SATURATED	LACUSTRINE AQUITARD
		Sub-Lacustrine Deposits		0-20	Fine Sands & Silts, Saturated Permeable	
		unconformable				
		GLACIAL TILL		0-10	Coarse to fine SAND, trace to some SILT, trace to some GRAVEL	LOWER AQUIFER
		unconformable				
		ANDOVER GRANITE		0-?	Medium to Coarse Grained Muscovite-Biotite Granite	BEDROCK AQUIFER

FIGURE 3. GENERALIZED GEOLOGIC AND HYDROGEOLOGIC COLUMN FOR HANSCOM AFB, MA.

BORING NUMBER HB-19  
 JOB NUMBER 11-9540  
 DATE STARTED 4-24-90  
 DATE COMPLETED 4-24-90  
 DRILLED BY TN  
 LOGGED BY KMP  
 CHECKED BY GPM

REMARKS: PAGE 1 OF 1  
 FLUSH MOUNTED WELL  
 SWL MEASURED 9.34' BELOW TOC ON 5/29/90  
 WELL ALIGNMENT TEST COMPLETED 5/18/90  
 HNU READINGS RECORDED IN "LAB TEST" COLUMN

ELEV. IN FEET	DEPTH IN FEET	DESCRIPTION	MONITORING WELL CONSTRUCTION	SYM- BOLS	LAB TESTS	SPT N VALUE
129.02	0.0	Firm yellowish brown (10 YR 5/6) to very pale brown (10 YR 7/3) fine to medium grained SAND (SP)				
					0	19
					0	22
122.02	7.0	Firm light brownish gray (2.5 YR 6/2) fine grained SAND (SP)			0	17
120.02	9.0	Very stiff light yellowish brown (2.5 Y 6/4) SILT (ML)			0	16
117.02	12.0	Very stiff light yellowish brown (2.5 Y 6/4) SILT with lenses of fine grained sand (ML)			0	17
113.52	15.5	Boring Terminated at 15.5'				16

FIGURE 4. TEST BORING RECORD FOR SOIL BORING IN THE VICINITY OF BUILDING 1812

BORING NUMBER HB-03  
 JOB NUMBER 11-9540  
 DATE STARTED 5-1-90  
 DATE COMPLETED 5-1-90  
 DRILLED BY TN  
 LOGGED BY KMP  
 CHECKED BY GPM

REMARKS:

PAGE 1 OF 1

FLUSH MOUNTED WELL  
 SWL MEASURED 3.05' BELOW TOC ON 5/29/90  
 WELL ALIGNMENT TEST COMPLETED 5/18/90  
 HNU READINGS RECORDED IN "LAB TEST" COLUMN



ELEV. IN FEET	DEPTH IN FEET	DESCRIPTION	MONITORING WELL CONSTRUCTION	SYM- BOLS	LAB TESTS	SPT N VALUE
132.00	0.0	Very stiff to hard light olive brown (2.5 Y 5/4) SILT (ML)			0	32
					0	20
					0	27
123.00	9.0	Firm yellowish brown (10 YR 5/6) fine to medium grained SAND with stratifications (SM)			0	17
120.00	12.0	Very stiff grayish brown (2.5 Y 5/2) clayey SILT (ML)			0	31
	13.0	Boring Terminated at 12.0'				

FIGURE 5. TEST BORING RECORD FOR SOIL BORING IN THE VICINITY OF BUILDING 1812

**APPENDIX B**

**ANALYTICAL REPORT FOR BUILDING 1639, BUILDING 1812,  
AND BACKGROUND AREA**

**@ AIR TOXICS LTD.**

AN ENVIRONMENTAL ANALYTICAL LABORATORY

**WORK ORDER #: 9210075**

## Work Order Summary

**CLIENT:** Mr. Jeff Kittel  
Battelle  
505 King Ave.  
Columbus, OH 43201

**BILL TO:** Accounts Payable  
Engineering Science  
1700 Broadway Ste. 900  
Denver, CO 80290

**PHONE:** 614-424-6122

**INVOICE #** 8630

**FAX:** 614-424-3667

**P.O. #** DE268.03.04

**DATE RECEIVED:**

10/14/92

**AMOUNT:** \$910.00

**DATE REPORTED:**

10/26/92

**PROJECT #** G4468-0640

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>Receipt</u> <u>VAC./Press.</u>	<u>PRICE</u>
01A	H1-A-2.5	TO-3	0 "Hg	\$120.00
02A	H1-A-5	TO-3	0 "Hg	\$120.00
03A	H1-B-2.5	TO-3	2.0 "Hg	\$120.00
04A	H1-B-5	TO-3	1.0 "Hg	\$120.00
05A	H1-C-3.5	TO-3	0.5 "Hg	\$120.00
06A	H1-C-6	TO-3	0.5 "Hg	\$120.00
07A	H1-BG-1.5-9	TO-3	1.0 "Hg	\$120.00
07B	H1-BG-1.5-9 Duplicate	TO-3	1.0 "Hg	NC
08A	Method Spike	TO-3	NA	NC
09A	Lab Blank	TO-3	NA	NC

Misc Charges 1 Liter SUMMA Canister Preparation (7) @ \$10.00 each. \$70.00

CERTIFIED BY Amelia J. Freeman  
Laboratory Director

DATE: 10/26/92

11325 SUNRISE GOLD CIRCLE, SUITE E • RANCHO CORDOVA, CA 95742

(916) 638-9892 • FAX (916) 638-9917



**AIR TOXICS LTD.**

SAMPLE NAME: H1-A-2.5

ID#: 9210075-01A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6101508	Date of Collection: 10/12/92	
Dil. Factor:		200	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.20	0.62	5.2	16
Toluene	0.20	0.74	4.2	15
Total Xylenes	0.20	0.85	2.9	12
Ethyl Benzene	0.20	0.85	1.1	4.7

**TOTAL PETROLEUM HYDROCARBONS  
GC/FID**

(Quantitated as Jet Fuel)

File Name:		6101508	Date of Collection: 10/12/92	
Dil. Factor:		200	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	2.0	8.0	5600	22000

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: H1-A-5

ID#: 9210075-02A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6101509		Date of Collection: 10/12/92	
Dil. Factor:		500		Date of Analysis: 10/15/92	
Compound	MDL	MDL	Amount	Amount	
	(ppmv)	(uG/L)	(ppmv)	(uG/L)	
Benzene	0.50	1.6	27	84	
Toluene	0.50	1.8	35	130	
Total Xylenes	0.50	2.1	30	130	
Ethyl Benzene	0.50	2.1	10	42	

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6101509		Date of Collection: 10/12/92	
Dil. Factor:		500		Date of Analysis: 10/15/92	
Compound		MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*		5.0	20	19000	76000

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: H1-B-2.5

ID#: 9210075-03A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6101510	Date of Collection: 10/12/92	
Dil. Factor:		220	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.22	0.69	2.8	8.7
Toluene	0.22	0.81	1.3	4.8
Total Xylenes	0.22	0.93	1.9	8.1
Ethyl Benzene	0.22	0.93	0.84	3.6

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6101510	Date of Collection: 10/12/92	
Dil. Factor:		220	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	2.2	8.8	2700	11000

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: H1-B-5

ID#: 9210075-04A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6101606		Date of Collection: 10/12/92	
Dil. Factor:		210		Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)	
Benzene	0.21	0.66	2.4	7.5	
Toluene	0.21	0.77	0.84	3.1	
Total Xylenes	0.21	0.89	1.5	6.4	
Ethyl Benzene	0.21	0.89	0.42	1.8	

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6101606		Date of Collection: 10/12/92	
Dil. Factor:		210		Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)	
TPH*	2.1	8.4	3200	13000	

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: H1-C-3.5

ID#: 9210075-05A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6101607	Date of Collection: 10/12/92	
Dil. Factor:		10	Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.010	0.031	0.44	1.4
Toluene	0.010	0.037	0.13	0.48
Total Xylenes	0.010	0.042	0.37	1.6
Ethyl Benzene	0.010	0.042	0.11	0.47

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6101607	Date of Collection: 10/12/92	
Dil. Factor:		10	Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.10	0.40	280	1100

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: H1-C-6

ID#: 9210075-06A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6101514	Date of Collection: 10/12/92	
Dil. Factor:		2100	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	2.1	6.6	11	34
Toluene	2.1	7.7	20	74
Total Xylenes	2.1	8.9	67	280
Ethyl Benzene	2.1	8.9	9.3	39

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6101514	Date of Collection: 10/12/92	
Dil. Factor:		2100	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	21	84	11000	44000

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: H1-BG-1.5-9

ID#: 9210075-07A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6101604	Date of Collection: 10/12/92	
Dil. Factor:		10	Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.010	0.031	0.16	0.50
Toluene	0.010	0.037	0.93	3.4
Total Xylenes	0.010	0.042	4.7	20
Ethyl Benzene	0.010	0.042	0.43	1.8

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6101604	Date of Collection: 10/12/92	
Dil. Factor:		10	Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.10	0.40	330	1300

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: H1-BG-1.5-9 Duplicate

ID#: 9210075-07B

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6101605	Date of Collection: 10/12/92	
Dil. Factor:		10	Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.010	0.031	0.16	0.50
Toluene	0.010	0.037	0.93	3.4
Total Xylenes	0.010	0.042	4.7	20
Ethyl Benzene	0.010	0.042	0.43	1.8

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Jet Fuel)

File Name:		6101605	Date of Collection: 10/12/92	
Dil. Factor:		10	Date of Analysis: 10/16/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.10	0.40	340	1400

\*TPH referenced to Jet Fuel (MW=156)



**AIR TOXICS LTD.**

SAMPLE NAME: Method Spike

ID#: 9210075-08A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6101602	Date of Collection:	10/12/92
Dil. Factor:		1.0	Date of Analysis:	10/16/92
	MDL	MDL		
Compound	(ppmv)	(uG/L)	% Recovery	
Benzene	0.001	0.003	90	
Toluene	0.001	0.004	83	
Total Xylenes	0.001	0.004	80	
Ethyl Benzene	0.001	0.004	80	

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Jet Fuel)

File Name:		6101603	Date of Collection:	10/12/92
Dil. Factor:		1.0	Date of Analysis:	10/16/92
	MDL	MDL		
Compound	(ppmv)	(uG/L)	% Recovery	
TPH*	0.010	0.040	110	

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: Lab Blank

ID#: 9210075-09A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6101501	Date of Collection: 10/12/92	
Dil. Factor:		1.0	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.001	0.003	Not Detected	Not Detected
Toluene	0.001	0.004	Not Detected	Not Detected
Total Xylenes	0.001	0.004	Not Detected	Not Detected
Ethyl Benzene	0.001	0.004	Not Detected	Not Detected

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6101501	Date of Collection: 10/12/92	
Dil. Factor:		1.0	Date of Analysis: 10/15/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.010	0.040	Not Detected	Not Detected

\*TPH referenced to Jet Fuel (MW=156)



11325 SUNRISE GOLD CIRCLE, SUITE 'E'  
RANCHO CORDOVA, CA 95742  
(916) 638-9892 • FAX (916) 638-9917

## CHAIN OF CUSTODY RECORD

Page \_\_\_\_ of \_\_\_\_

PROJECT # 64468-0640 PO #           
REMARKS         

COLLECTED BY (Signature) MAT/TA

FIELD SAMPLE I.D.#	SAMPLING MEDIA (Tenax, Canister etc.)	DATE/TIME	ANALYSIS	VAC./PRESSURE	LAB I.D.#
H1-A-2.5	Canister	12 Oct / 0900	BTEX / TVH	0" Hg	
H1-A-5	"	"	"	0" Hg	
H1-B-2.5	"	"	"	2.0" Hg	
H1-B-5	"	"	"	1" Hg	
H1-C-3.5	"	"	"	0.5" Hg	
H1-C-6	"	"	"	0.5" Hg	
H1-BG-7.5	"	"	"	1" Hg	

RELINQUISHED BY: DATE/TIME

RECEIVED BY: DATE/TIME

RELINQUISHED BY: DATE/TIME

RECEIVED BY: DATETIME

NAME	DATE	TIME	RECEIVED BY	DATE/TIME
JAMES E. HUBBARD	10/13/92	11:22 AM	Ally's Messenger	10/14/92
				09/15

**LAB USE ONLY**

SHIPPER NAME

**AIR BILL #**

OPENED BY: DATE/TIME

TEMP(°C)

## CONDITION

REMARKS



ENGINEERING-SCIENCE, INC.

BERKELEY LABORATORY  
600 BANCROFT WAY  
BERKELEY, CA 94710  
Tel: (415) 841-7353

Report Date: November 19, 1992

Work Order No.: 4432

Client: Doug Downey  
ES Denver/AFCEE/Hanscom AFB  
1700 Broadway  
Denver, CO 80290

Date of Sample Receipt: 10/06/92

Your soil samples identified as:

H1-VW-4'-4.5'  
H1-VW-4.5'-5.0'  
H1-A-3'-4'  
H2-VW-3'-3.5'  
H2-VW-4'-4.5'  
H1-BRG-2.5'-3'

were analyzed for BTEX by EPA Method 8020, TRPH by EPA Method 418.1, TKN, total phosphorus, soil classification, pH, alkalinity, iron and moisture.

The analytical reports for the samples listed above are attached.

**GC VOLATILES DATA PACKAGE**

VOLATILE ORGANICS CASE NARRATIVE

WORK ORDER NO. 4432

<sup>11/19/92</sup>  
EPA METHOD 8020

Sample H1-VW-S<sup>3</sup>-3.5' (4432-04) was run as a medium level due to the presence of high concentrations of non-target analytes.

GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.:4452

% Moisture: 22.21

Client ID:HI-UW-4'-4.5'

Matrix:SOIL

Laboratory ID:4452-1

Level:LOW

Date Collected: 10/02/92

Unit:UG/KG

Dilution Factor: 1

Date Analyzed:10/15/92

Date Confirmed:NA

=====

Compound	Result	Reporting Limit
=====		

Benzene	48.0 D=5	0.6
Ethyl Benzene	17.0	0.6
Toluene	20.0	0.9
Xylenes (total)	20.0	1.2

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: *AB*

GROUP LEADER: *hwa*

GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.:4432

% Moisture: 21.81

Client ID:HI-VW-4.5'-5.0'

Matrix:SOIL

Laboratory ID:4432-2

Level:MEDIUM

Date Collected: 10/02/92

Unit:UG/KG

Dilution Factor: 1

Date Analyzed:10/14/92  
Date Confirmed:NA

=====

Compound	Result	Reporting Limit
=====		
Benzene	670.0	77.0
Ethyl Benzene	450.0	64.0
Toluene	270.0	90.0
Xylenes (total)	450.0	120.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AB

GROUP LEADER:

*Handwritten signature*



GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.:4432

% Moisture: 5.81

Client ID:HI-A-3'-4'

Matrix:SOIL

Laboratory ID:4432-3

Level:MEDIUM

Date Collected: 10/02/92

Unit:UG/KG

Dilution Factor: 2

Date Analyzed:10/14/92

Date Confirmed:NA

Compound

Result

Reporting  
Limit

Benzene

1000.0

130.0

Ethyl Benzene

1300.0

110.0

Toluene

4500.0

150.0

Xylenes (total)

12000.0

190.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AB

GROUP LEADER: *hroal*

GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.: 4432

% Moisture: 3.2

Client ID: HZ-UV-3'-3.5' *TP 11/18/92*

Matrix: SOIL

Laboratory ID: 4432-4

Level: MEDIUM

Date Collected: 10/03/92

Unit: UG/KG

Dilution Factor: 1

Date Analyzed: 10/14/92

Date Confirmed: NA

=====

Compound	Result	Reporting Limit
----------	--------	--------------------

=====

Benzene	ND	52.0
Ethyl Benzene	ND	52.0
Toluene	ND	72.0
Xylenes (total)	ND	93.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *AS*GROUP LEADER: *brock*

GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.: 4452

% Moisture: 6.14

Client ID: H2-VW-4/-4.5/

Matrix: SOIL

Laboratory ID: 4452-5

Level: LOW

Date Collected: 10/05/92

Unit: UG/KG

Dilution Factor: 5

Date Analyzed: 10/15/92

Date Confirmed: NA

=====

Compound	Result	Reporting Limit
Benzene	ND	5.2
Ethyl Benzene	ND	2.6
Toluene	15.0	5.7
Xylenes (total)	51.0	4.8

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AS

GROUP LEADER: *Wood*

-----  
GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.:4432

% Moisture:NA

Client ID:HI-BKG-2.5'-5'

Matrix:SOIL

Laboratory ID:4432-7

Level:LOW

Date Collected: 10/04/92

Unit:UG/KG

Dilution Factor: 1

Date Analyzed:10/13/92  
Date Confirmed:NA=====ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *AD*GROUP LEADER: *front*

GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.:4432

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:MSUG4921015

Level:LOW

Date Collected: NA

Unit:UG/KG

Dilution Factor: 1

Date Analyzed:10/15/92  
Date Confirmed:NA

Compound	Result	Reporting Limit
Benzene	ND	0.6
Ethyl Benzene	ND	0.5
Toluene	ND	0.7
Xylenes (total)	ND	0.9

ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *AS*GROUP LEADER: *Amel*

-----  
GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.:4432

% Moisture:NA

Client ID:METH00 BLANK

Matrix:SOIL

Laboratory ID:MWUG4921014

Level:MEDIUM

Date Collected: NA

Unit:UG/KG

Dilution Factor: 1

Date Analyzed:10/14/92

Date Confirmed:NA  
=====

Compound

Result

Reporting  
Limit  
=====

Benzene

ND

60.0

Ethyl Benzene

ND

50.0

Toluene

ND

70.0

Xylenes (total)

ND

90.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AS

GROUP LEADER: 

GC ANALYTICAL REPORT  
Analytical Method  
BTEX Aromatic Compounds

Work Order NO.:4452

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:M5064921015

Level:LOW

Date Collected: NA

Unit:UG/KG

Dilution Factor: 1

Date Analyzed:10/15/92

Date Confirmed:NA

Compound	Result	Reporting Limit
Benzene	ND	0.6
Ethyl Benzene	ND	0.5
Toluene	ND	0.7
Xylenes (total)	ND	0.9

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AB

GROUP LEADER: 

ES-ENGINEERING SCIENCE, INC.

600 BANCROFT WAY  
BERKELEY, CA 94710

GC ANALYTICAL REPORT  
ANALYTICAL REPORT  
BTEX AROMATIC COMPOUNDS

MATRIX: SOIL

DATE: 10/14/92

LABORATORY NO.

CLIENT ID

a-a-a-TriFluoro  
Toluene

NWUG4921014

METHOD BLANK

91

4452-2

HI-UW-4.5'-5.0'

62

4432-3

HI-A-3'-4'

115

4452-4

H<sub>2</sub>-UW-3'-3.5'

122

2  
TP 11/18



ES-ENGINEERING SCIENCE, INC.

600 BANCROFT WAY  
BERKELEY, CA 94710

GC ANALYTICAL REPORT  
ANALYTICAL REPORT  
BTEX AROMATIC COMPOUNDS

MATRIX: SOIL

DATE: 10/13&15/92

LABORATORY NO.

CLIENT ID

a-a-a-TriFluoro  
Toluene

MSUG4921013	METHOD BLANK	94
4432-7	HI-BKG-2.5'-3'	114
4435-1	KAFB66-SB1-SS3-5-5.5'	108
MSUG4921015	METHOD BLANK	79
4432-1	HI-VW-4'-4.5'	118
4432-1DIL	HI-VW-4'-4.5'DIL	104
4432-5	HI-VW-4'-4.5'	70
4451-1	MC-VW-7	109

TP 11/18

ES-ENGINEERING SCIENCE, INC.

600 Bancroft Way  
Berkeley, CA 94710

-----  
QUALITY CONTROL RESULTS SUMMARY  
ANALYTICAL REPORT  
BTEX AROMATIC COMPOUNDS

Work Order No.: 4432,4451,4455

QC sample No.: 55UG4921009A&B

Date analyzed: 10/09/92

Matrix: SOIL

Dilution factor: 1

*****									
COMPOUND	SA	SR	MS	PR	MSD	PR	RPD	QC LIMITS	
8010 analysis	UG/KG	UG/KG	UG/KG		UG/KG			RPD	PR
*****									
COMPOUND	SA	SR	MS	PR	MSD	PR	RPD	QC LIMITS	
8020 analysis	UG/KG	UG/KG	UG/KG		UG/KG			RPD	PR
*****									
Benzene	20	ND	22.6	113	23.5	118	4	29	39-150
Toluene	20	ND	21.4	107	22.2	111	4	28	46-148
*****									

MS = Spike sample  
MSD = Spike sample duplicate  
SR = Sample result  
SA = Spike added  
ND = Not Found At or Above Detection Limits

NC = Not calculated  
NA = Not Applicable  
\*\* = Out of limits

$RPD = 100 \times (MS - MSD) / ((MS + MSD) / 2)$

$PR = 100 \times ((MS \text{ or } MSD) - SR) / SA$

ANALYST: *AB*

QC: *MMB*

ES-ENGINEERING SCIENCE, INC.

600 Bancroft Way  
Berkeley, CA 94710

-----  
QUALITY CONTROL RESULTS SUMMARY  
ANALYTICAL REPORT  
BTEX AROMATIC COMPOUNDS

Work Order No.: 4432,4451,4435

QC sample No.: SWUG4921016A&B

Date analyzed: 10/16/92

Matrix: SOIL

Dilution factor: 1

*****									
COMPOUND	SA	SR	MS	PR	MSD	PR	RPD	QC LIMITS	
8010 analysis	UG/KG	UG/KG	UG/KG		UG/KG			RPD	PR
*****									
COMPOUND	SA	SR	MS	PR	MSD	PR	RPD	QC LIMITS	
8020 analysis	UG/KG	UG/KG	UG/KG		UG/KG			RPD	PR
*****									
Benzene	2000	ND	2000	100	1640	82	20	29	39-150
Toluene	2000	ND	2600	130	2700	135	4	28	46-148
*****									

MS = Spike sample  
MSD = Spike sample duplicate  
SR = Sample result  
SA = Spike added  
ND = Not Found At or Above Detection Limits

NC = Not calculated  
NA = Not Applicable  
\*\* = Out of limits

$RPD = 100 \times (MS - MSD) / ((MS + MSD) / 2)$

$PR = 100 \times ((MS \text{ or } MSD) - SR) / SA$

ANALYST: *Atz*

QC: *RWB*

# METHOD BLANK SUMMARY

WD # 4432,4451,4435

LAB NAME : ENGINEERING-SCIENCE, INC.

DATE ANALYZED 10/13&15/92

LAB SAMPLE ID:MSUG4921013&15

DATE EXTRACTED : NA

MATRIX :LOW SOIL

INSTRUMENT ID:VGC-4

LAB SAMPLE ID	CLIENT SAMPLE ID	DATE ANALYZED
MSUG4921013	METHOD BLANK	10/13/92
4432-7	HI-BKG-2.5'-3'	10/13/92
4435-1	KAFB66-SB1-SS3-5-5.5'	10/13/92
MSUG4921013 <sup>2</sup>	METHOD BLANK	10/15/92
4432-1	HI-VW-4'-4.5'	10/15/92
4432-1DIL	HI-VW-4'-4.5'DIL	10/15/92
4432-5	HI-VW-4'-4.5'	10/15/92
4451-1	MC-VW-7	10/15/92

TP 11/14

# METHOD BLANK SUMMARY

WU # 4432

LAB NAME : ENGINEERING-SCIENCE, INC.

DATE ANALYZED : 10/14/92

LAB SAMPLE ID: MWUG4921014

DATE EXTRACTED : NA

MATRIX : SOIL

INSTRUMENT ID: UGC-4

LAB SAMPLE ID	CLIENT SAMPLE ID	DATE ANALYZED
MWUG4921014	METHOD BLANK	10/14/92
4432-2	HI-UW-4.5'-5.0'	10/14/92
4432-3	HI-A-3'-4'	10/14/92
4432-4	HI-UW-3'-3.5'	10/14/92

4011/18

**TOTAL RECOVERABLE PETROLEUM HYDROCARBONS**

**DATA PACKAGE**

ES-ENGINEERING SCIENCE, INC.

600 Bancroft Way  
Berkeley, CA 94710

=====

ORGANIC ANALYTICAL REPORT

Work Order NO.: 4432

Parameter: TPH

Matrix: Soil

Analytical

Unit: mg/Kg

Method: 418.1

Date Extracted 10/27/92

QC Batch NO.: S92QCB026TPH

Date Analyzed: 10/29/92

=====

Sample ID:	Client ID:	Result	Reporting Limit	Percent Moisture
4432-01	HI-VW-4'-4.5'	22	5	22.2
4432-02	HI-VW-4.5'-5.0'	15	5	21.8
4432-03	HI-A-3'-4'	ND	4	5.8
4432-04	<i>TP</i> H2-VW-3'-3.5'	12	4	3.2
4432-05	<i>11/18</i> H2-VW-4'-4.5'	13000	4	6.1
4432-07	HI-BKG-2.5'-3'	84	5	11.4
MSTPH921027	METHOD BLANK	ND	4	NA

=====

NA\_ Not Analyzed

ND\_ Not Detected

ANALYST:

*Stan. J.*

GROUP LEADER:

*Robert*

**INORGANICS DATA PACKAGE**



## INORGANICS ANALYTICAL REPORT

Client: ES-Denver  
Project: AFCEEWork Order: 4432  
Matrix: SolidClient's ID: ~~HZ~~<sup>TP 11/18/92</sup>-VW    ~~HZ~~<sup>TP 11/18/92</sup>-VW    HI-BKG  
                 -3'-3.5'    -4'-4.5'    -2.5'-3'

Sample Date: 10/03/92    10/03/92    10/04/92

% Moisture:

Lab ID: 4432.04    4432.05    4432.06

Parameter	-----Results-----	Method	Normal Report Limit	Units	Date Analyzed
Alkalinity	90.                      ND                      ND	SM 403(M)	50	mg/Kg CaCO3	11/02/92
Moisture	3.2                      6.1                      9.3	ASTM D2216	.1	% by wt	10/22/92
pH	7.0                      6.2                      6.6	EPA 9045	NA	pH Units	10/27/92

Note: Samples for alkalinity analysis were extracted using 10mL water for each 1g sample. These water extracts were analyzed for alkalinity, and the results were calculated in the solid on a dry-weight basis.

NA- Not Applicable

ND- Not Detected

ANALYST: Don GleasonGROUP LEADER: William S. Smith

## INORGANICS ANALYTICAL REPORT

Client: ES-Denver  
Project: AFCEEWork Order: 4432  
Matrix: SolidClient's ID: HI-VW HI-VW HI-A  
-4'-4.5' -4.5'-5.0' -3'-4'Sample Date: 10/02/92 10/02/92 10/02/92  
% Moisture:  
Lab ID: 4432.01 4432.02 4432.03

Parameter	-----Results-----	Method	Normal Report Limit	Units	Date Analyzed
Alkalinity	ND ND ND	SM 403(M)	50	mg/Kg CaCO3	11/02/92
Moisture	22.2 21.8 5.8	ASTM D2216	.1	% by wt	10/22/92
pH	5.8 6.0 6.1	EPA 9045	NA	pH Units	10/27/92

Note: Samples for alkalinity analysis were extracted using 10mL water for each 1g sample. These water extracts were analyzed for alkalinity, and the results were calculated in the solid on a dry-weight basis.

NA- Not Applicable  
ND- Not DetectedANALYST: Don HeatonGROUP LEADER: 

## INORGANIC QC SUMMARY - MS and MSD

Work Order: 4432

% Moisture: NA

Alkalinity Moisture pH  
 Lab ID Spk/Dup: Blank Spk 4438.04 4454.01  
 QC Batch: 452.42 451.82 453.40

Matrix: Solid

Units: mg/Kg CaCO<sub>3</sub> (Alk)  
 % by wt. (Mois)  
 pH Units (pH)

Parameter	Date Analyzed MS/Dup	-----Results-----			RPD	RPD QC Limit	-Conc Added-		Percent Recovered	
		Unspiked Sample	MS/Sample	MSD/Dup			MS	MSD	MS	MSD
Alkalinity	11/02/92	0.00	23000.00	23000.00	0	20	23650.00	23650.00	97	97
Moisture	10/22/92		8.33	7.52	11	20				
pH	10/27/92		5.95	6.08	2	20				

\* or N = Outside QC Limit:

QC Limits for % Rec: 75 - 125

ANALYST:

*Don Meator*

Date

*11/11/92*

REVIEWER:

*ANB*

Date

*11/17/92*

File:MIQCHSWH

## INORGANICS ANALYTICAL REPORT

Client: ES-Denver  
Project: AFCEEWork Order: 4432  
Matrix: SolidClient's ID: Prep  
Blank

Sample Date:

% Moisture:

Lab ID: Prep Blank

Parameter	-----Results-----	Method	Normal Report Limit	Units	Date Analyzed
Alkalinity	ND	SM 403(M)	50	mg/Kg CaCO3	11/02/92
Moisture	NA	ASTM D2216	.1	% by wt	10/22/92
pH	NA	EPA 9045	NA	pH Units	10/27/92

Note: Samples for alkalinity analysis were extracted using 10mL water for each 1g sample. These water extracts were analyzed for alkalinity, and the results were calculated in the solid on a dry-weight basis.

NA- Not Applicable  
ND- Not DetectedANALYST: Don ClintonGROUP LEADER: Michael S. Gandy

## INORGANICS QC SUMMARY - LAB CONTROL SAMPLE

Work Order: 4432 % Moisture: NA  
Lab ID of LCS: Matrix: Solid  
Alkalinity: 452.42 LCS Units: mg/Kg CaCO3

Parameter	Date Analyzed LCS	LCS Result	Conc Added	% Rec LCS	Advisory Limits	
					-- % Rec -- Low	High
Alkalinity	11/02/92	23000.00	23650.00	97	80	120

ANALYST: Don GleasonDate 11/11/92REVIEWER: NWBDate 11/17/92

File: M1QCLCSW

**METALS DATA PACKAGE**

CASE NARRATIVE  
WORK ORDER NO. 4432  
METALS

The serial dilution sample result for iron did not agree with the undiluted result within 10%, and the diluted sample result was greater than ten times the iron MDL. All iron results in this batch are therefore flagged with "E".

Client ID's were abridged by the laboratory to facilitate computer entry of analytical data. The following should be used as a reference:

<u>CLIENT ID</u>	<u>ABRIDGED ID</u>
H1-VW-4'-4.5'	H1VW-4
H1-VW-4.5'-5.0'	VW-4.5
H1-A-3'-4'	A-3-4
H2-VW-3'-3.5'	VW-3
H2-VW-4'-4.5'	H2VW-4
H1-BKG-2.5'-3'	BKG2.5





CLIENT SAMPLE ID

## VW-4.5

CLIENT SAMPLE ID

A-3-4

Concentration Units (ug/L or mg/kg dry weight): MG/KG

[illegible]

**Comments:**

CLIENT SAMPLE ID

## VW-3



## INORGANIC ANALYSES DATA SHEET

BKG2.5

## INORGANIC ANALYSES DATA SHEET

CLIENT SAMPLE ID

PBLANK

Lab Name: E\_S\_\_BERKELEY LABORATORY\_\_ Contract: AFCEE\_ES-D

Lab Code: ESBL\_\_ Case No.: 4432S SAS No.: \_\_\_\_\_ SDG No.: A-3-4\_\_

Matrix (soil/water): SOIL\_

Lab Sample ID: PBK 482.22

Level (low/med): LOW\_\_

Date Sampled : 11/04/92

% Solids:	100.0
-----------	-------

Concentration Units (ug/L or mg/kg dry weight): MG/KG

[illegible]

Comments:

## LABORATORY CONTROL SAMPLE (BLANK SPIKE)

Contract: AFCEE\_ES-D

SDG No.: A-3-4

Solid LCS Source: ESBL-LCSS

Aqueous LCS Source: \_\_\_\_\_

FORM VII - IN

## LABORATORY CONTROL SAMPLE (BLANK SPIKE)

Aqueous LCS Source: \_\_\_\_\_

3 / 90



CLIENT SAMPLE ID

BLANK SPIKE DUPLICATE

LCSSD

Contract: AFCEE ES-D

SDG No.: A-3-4

Level (low/med): LOW

% Solids for Duplicate: 100.0

Concentration Units (ug/L or mg/kg as received):MG/KG

[illegible]

## ICP SERIAL DILUTION

H1VW-4L

Matrix (soil/water): SOIL\_ Level (low/med): LOW\_

[illegible]

## Method Detection Limits (Annually)

Contract: AFCEE\_ES-D

Case No. : 4432S

SAS No. : \_\_\_\_\_

SDG No.: A-3-4

TJA 61 M

Date: 08/31/92

Flame AA ID Number : \_\_\_\_\_

Matrix: SOIL

Turnace AA ID Number :

(ug/L in 1.00g to 100ml digestate)

[illegible]

Comments:



Engineering Science - Berkeley Laboratory  
Inorganics Report

ANALYSIS RUN LOG

Lab Name: E\_S\_BERKELEY\_LABORATORY\_

Contract: AFCEE\_ES-D

Lab Code: ESBL\_ Case No.: 4432S\_

SAS No.: \_\_\_\_\_ SDG No.: A-3-4\_

Instrument ID Number: TJA 61 M\_

Method: P\_

Start Date: 11/09/92

End Date: 11/09/92

EPA Sample No.	D/F	Time	% R	Analytes																	
				F	E																
STD1	1.00	1027		X																	
STD2	1.00	1031		X																	
STD3	1.00	1036		X																	
STD4	1.00	1041		X																	
ICV	1.00	1045		X																	
ICB	1.00	1050		X																	
ICSA	1.00	1054		X																	
ICSAB	1.00	1059		X																	
CRI	1.00	1104																			
ZZZZZZ	1.00	1108																			
PBLANK	1.00	1113		X																	
LCSS	1.00	1117		X																	
LCSSD	1.00	1122		X																	
H1VW-4	1.00	1127		X																	
H1VW-4L	1.00	1131		X																	
CCV	1.00	1136		X																	
CCB	1.00	1141		X																	
VW-4.5	1.00	1145		X																	
A-3-4	1.00	1150		X																	
VW-3	1.00	1154		X																	
H2VW-4	1.00	1159		X																	
BKG2.5	1.00	1204		X																	
VW-7	1.00	1208		X																	
MPB-9	1.00	1213		X																	
MPA-9	1.00	1217		X																	
CCV	1.00	1222		X																	
CCB	1.00	1227		X																	
VW-10	1.00	1231		X																	
VMP2-9	1.00	1236		X																	
VMP1-9	1.00	1241		X																	
ICSA	1.00	1245		X																	
ICSAB	1.00	1250		X																	



TOTAL PHOSPHORUS

TOTAL KJELDAHL NITROGEN

SOIL CLASSIFICATION

DATA PACKAGE



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil  
Analysis for: Percent Solids  
First Sample #: 210-0637

Sampled: 9/2-4/92  
Received: Oct 7, 1992  
Analyzed: Oct 19, 1992  
Reported: Oct 20, 1992

## LABORATORY ANALYSIS FOR: Percent Solids

Sample Number	Sample Description	Detection Limit %	Sample Result %
210-0637	H1-VW-4'-4.5'	10	83
210-0638	H1-VW-4.5'-5.0'	10	84
210-0639	H1-A-3'-4'	10	94
210-0640	H2-VW-3'-3.5'	10	97
210-0641	H2-VW-4'-4.5'	10	92
210-0642	H1-BKG-2.5'-3'	10	92

THIS REPORT HAS BEEN  
APPROVED AND REVIEWED BY

*Paulson* 11/18/92

ESBL PROJECT MANAGER

DATE

Analytes reported as N.D. were not present above the stated limit of detection.

SEQUOIA ANALYTICAL

*Granicher*  
Tod Granicher  
Project Manager

2100637.ENG <7>





# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil  
Analysis for: Total Phosphorous  
First Sample #: 210-0637

Sampled: 9/2-4/92  
Received: Oct 7, 1992  
Analyzed: Oct 19, 1992  
Reported: Oct 20, 1992

## LABORATORY ANALYSIS FOR: Total Phosphorous

Sample Number	Sample Description	Detection Limit mg/kg	Sample Result mg/kg
210-0637	H1-VW-4'-4.5'	10	370
210-0638	H1-VW-4.5'-5.0'	10	290
210-0639	H1-A-3'-4'	10	300
210-0640	H2-VW-3'-3.5'	10	450
210-0641	H2-VW-4'-4.5'	10	600
210-0642	H1-BKG-2.5'-3'	10	460
-	Method Blank	1.0	N.D.

Analytes reported as N.D. were not present above the stated limit of detection.

SEQUOIA ANALYTICAL

Tod Granicher  
Project Manager

Please Note:

Analysis results reported on a dry-weight basis.

2100637.ENG <8>



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil  
Analysis for: Total Kjeldahl Nitrogen  
First Sample #: 210-0637

Sampled: 9/2-4/92  
Received: Oct 7, 1992  
Analyzed: Oct 15, 1992  
Reported: Oct 20, 1992

## LABORATORY ANALYSIS FOR: Total Kjeldahl Nitrogen

Sample Number	Sample Description	Detection Limit mg/kg	Sample Result mg/kg
210-0637	H1-VW-4'-4.5'	20	1,100
210-0638	H1-VW-4.5'-5.0'	20	730
210-0639	H1-A-3'-4'	20	70
210-0640	H2-VW-3'-3.5'	20	66
210-0641	H2-VW-4'-4.5'	20	53
210-0642	H1-BKG-2.5'-3'	20	91
-	Method Blank	0.10	N.D.

Analytes reported as N.D. were not present above the stated limit of detection.

SEQUOIA ANALYTICAL

  
Tod Granicher  
Project Manager

Please Note:

Analysis results reported on a dry-weight basis.

2100637.ENG <9>



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.

Client Project ID: W.O. #4432

600 Bancroft Way  
Berkeley, CA 94710

Attention: Tom Paulson

QC Sample Group: 210-0637-42

Reported: Oct 20, 1992

## QUALITY CONTROL DATA REPORT

ANALYTE	Total Phosphorous	Total Kjeldahl Nitrogen

Method:	EPA365.3	EPA351.4
Analyst:	K. Follett	G. Kern
Reporting Units:	mg/kg	mg/kg
Date Analyzed:	Oct 19, 1992	Oct 15, 1992
QC Sample #:	210-0642	210-0642

Sample Conc.:	420	84
Spike Conc. Added:	100	4000
Conc. Matrix Spike:	560	4000
Matrix Spike % Recovery:	140	98
Conc. Matrix Spike Dup.:	530	3800
Matrix Spike Duplicate % Recovery:	110	93
Relative % Difference:	5.6	5.1

SEQUOIA ANALYTICAL

Tod Granicher  
Project Manager

% Recovery:	$\frac{\text{Conc. of M.S.} - \text{Conc. of Sample}}{\text{Spike Conc. Added}} \times 100$
Relative % Difference:	$\frac{\text{Conc. of M.S.} - \text{Conc. of M.S.D.}}{(\text{Conc. of M.S.} + \text{Conc. of M.S.D.}) / 2} \times 100$

2100637.ENG <10>



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil, H1-VW-4'-4.5'  
Method of Analysis: ASTM D422-63  
Lab Number: 210-0637

Sampled: Sep 2, 1992  
Received: Oct 7, 1992  
Analyzed: Oct 13, 1992  
Reported: Oct 20, 1992

## PARTICLE SIZE DISTRIBUTION BY SIEVE AND HYDROMETER

### SIEVE TEST

- (A) TOTAL WEIGHT OF SAMPLE:  
(B) WEIGHT RETAINED IN NO. 10 SIEVE:  
(C) % PASSING NO. 10 SIEVE:

218.37g
33.38g
84.71

SIEVE TEST FOR  
WEIGHT RETAINED  
IN NO. 10 SIEVE

IDEAL PAN = 0.0  
IDEAL TOTAL = (B)

SIEVE SIZE	WEIGHT RETAINED, g	% RETAINED	CUMULATIVE % RETAINED	CUMULATIVE % PASSING
1 1/2 in.	0.0	0.0	0.0	100
3/8 in.	7.00	3.21	3.21	96.79
No. 4	10.54	4.83	8.04	91.96
No. 10	15.84	7.25	15.29	84.71
PAN	0.0			
TOTAL	33.38			

### HYDROMETER TEST

ELAPSED TIME (T)	TEMP. °C	HYDROMETER READING (H)	CORRECTED READING (R)	(L)	PARTICLE DIAM. (S)	% SUSPENDED (P)
2	21	20	16	13.7	0.035	21
5	21	17	13	14.2	0.023	17
10	21	15	11	14.5	0.016	15
15	21	15	11	14.5	0.013	15
25	21	13	9	14.8	0.010	12
40	21	12	8	15.0	0.0083	11
60	21	11	7	15.2	0.0068	9.3
90	21	11	7	15.2	0.0055	9.3
120	21	10	6	15.3	0.0048	8.0
1440	21	8	4	15.6	0.0014	5.3

WEIGHT OF SOIL USED IN HYDROMETER TEST (D):  
HYGROSCOPIC MOISTURE CORRECTION FACTOR (G):  
SPECIFIC GRAVITY (ASSUMED):  
DISPERSING AGENT CORRECTION FACTOR (E):  
MENISCUS CORRECTION FACTOR (F):  
TEMP./SPEC. GRAVITY DEPENDANT CONSTANT (K):

65g
0.983
2.65
3
1
0.01348

#### FORMULAS:

$R = H - E - F$   
 $S = K [ \text{SQRT} (L / T) ]$   
 $P = (R / W) 100$   
 $W = (J \cdot 100) / C$   
 $J = D \cdot G$

SEQUOIA ANALYTICAL

  
Tod Granicher  
Project Manager



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil, H1-VW-4.5'-5.0'  
Method of Analysis: ASTM D422-63  
Lab Number: 210-0638

Sampled: Sep 2, 1992  
Received: Oct 7, 1992  
Analyzed: Oct 13, 1992  
Reported: Oct 20, 1992

## PARTICLE SIZE DISTRIBUTION BY SIEVE AND HYDROMETER

### SIEVE TEST

- (A) TOTAL WEIGHT OF SAMPLE:  
(B) WEIGHT RETAINED IN NO. 10 SIEVE:  
(C) % PASSING NO. 10 SIEVE:

255.17g
4.75g
98.14

SIEVE TEST FOR  
WEIGHT RETAINED  
IN NO. 10 SIEVE

IDEAL PAN = 0.0  
IDEAL TOTAL = (B)

SIEVE SIZE	WEIGHT RETAINED, g	% RETAINED	CUMULATIVE % RETAINED	CUMULATIVE % PASSING
1 1/2 in.	0.0	0.0	0.0	100
3/8 in.	0.0	0.0	0.0	100
No. 4	1.48	0.59	0.59	99.42
No. 10	3.27	1.28	1.86	98.14
PAN	0.0			
TOTAL	4.75			

### HYDROMETER TEST

ELAPSED TIME (T)	TEMP. °C	HYDROMETER READING (H)	CORRECTED READING (R)	(L)	PARTICLE DIAM. (S)	% SUSPENDED (P)
2	21	12	8	15.0	0.037	12
5	21	10	6	15.3	0.024	9.2
10	21	9	5	15.5	0.017	7.6
15	21	8	4	15.6	0.014	6.1
25	21	8	4	15.6	0.011	6.1
40	21	8	4	15.6	0.0084	6.1
60	21	7	3	15.8	0.0069	4.6
90	21	7	3	15.8	0.0056	4.6
120	21	7	3	15.8	0.0049	4.6
1440	21	7	3	15.8	0.0014	4.6

WEIGHT OF SOIL USED IN HYDROMETER TEST (D):  
HYGROSCOPIC MOISTURE CORRECTION FACTOR (G):  
SPECIFIC GRAVITY (ASSUMED):  
DISPERSING AGENT CORRECTION FACTOR (E):  
MENISCUS CORRECTION FACTOR (F):  
TEMP./SPEC. GRAVITY DEPENDANT CONSTANT (K):

65g
0.983
2.65
3
1
0.01348

FORMULAS:  
 $R = H - E - F$   
 $S = K [ \text{SQRT} (L / T) ]$   
 $P = (R / W) 100$   
 $W = (J \cdot 100) / C$   
 $J = D \cdot G$

SEQUOIA ANALYTICAL

  
Tod Granicher  
Project Manager



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil, H1-A-3'-4'  
Method of Analysis: ASTM D422-63  
Lab Number: 210-0639

Sampled: Sep 2, 1992  
Received: Oct 7, 1992  
Analyzed: Oct 13, 1992  
Reported: Oct 20, 1992

## PARTICLE SIZE DISTRIBUTION BY SIEVE AND HYDROMETER

### SIEVE TEST

- (A) TOTAL WEIGHT OF SAMPLE:  
(B) WEIGHT RETAINED IN NO. 10 SIEVE:  
(C) % PASSING NO. 10 SIEVE:

256.56g
99.81g
61.1

SIEVE TEST FOR  
WEIGHT RETAINED  
IN NO. 10 SIEVE

IDEAL PAN = 0.0  
IDEAL TOTAL = (B)

SIEVE SIZE	WEIGHT RETAINED, g	% RETAINED	CUMULATIVE % RETAINED	CUMULATIVE % PASSING
1 1/2 in.	0.0	0.0	0.0	100
3/8 in.	41.21	16.06	16.06	83.94
No. 4	26.13	10.18	26.24	73.76
No. 10	32.47	12.65	38.90	61.10
PAN	0.0			
TOTAL	99.81			

### HYDROMETER TEST

ELAPSED TIME (T)	TEMP. °C	HYDROMETER READING (H)	CORRECTED READING (R)	(L)	PARTICLE DIAM. (S)	% SUSPENDED (P)
2	21	14	10	14.7	0.037	9.4
5	21	12	8	15.0	0.023	7.6
10	21	11	7	15.2	0.017	6.6
15	21	10	6	15.3	0.014	5.7
25	21	9	5	15.5	0.011	4.7
40	21	9	5	15.5	0.0094	4.7
60	21	7	3	15.8	0.0069	2.8
90	21	7	3	15.8	0.0056	2.8
120	21	7	3	15.8	0.0049	2.8
1440	21	7	3	15.8	0.0014	2.8

WEIGHT OF SOIL USED IN HYDROMETER TEST (D):  
HYGROSCOPIC MOISTURE CORRECTION FACTOR (G):  
SPECIFIC GRAVITY (ASSUMED):  
DISPERSING AGENT CORRECTION FACTOR (E):  
MENISCUS CORRECTION FACTOR (F):  
TEMP./SPEC. GRAVITY DEPENDANT CONSTANT (K):

65g
0.995
2.65
3
1
0.01348

FORMULAS:  
 $R = H - E - F$   
 $S = K [ \text{SQRT} (L / T) ]$   
 $P = (R / W) 100$   
 $W = (J \cdot 100) / C$   
 $J = D \cdot G$

SEQUOIA ANALYTICAL

  
Tod Granicher  
Project Manager



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil, H1-BKG-2.5'-3'  
Method of Analysis: ASTM D422-63  
Lab Number: 210-0642

Sampled: Sep 4, 1992  
Received: Oct 7, 1992  
Analyzed: Oct 14, 1992  
Reported: Oct 20, 1992

## PARTICLE SIZE DISTRIBUTION BY SIEVE AND HYDROMETER

### SIEVE TEST

- (A) TOTAL WEIGHT OF SAMPLE:  
(B) WEIGHT RETAINED IN NO. 10 SIEVE:  
(C) % PASSING NO. 10 SIEVE:

280.69g
39.34g
85.98

SIEVE TEST FOR  
WEIGHT RETAINED  
IN NO. 10 SIEVE

IDEAL PAN = 0.0  
IDEAL TOTAL = (B)

SIEVE SIZE	WEIGHT RETAINED, g	% RETAINED	CUMULATIVE % RETAINED	CUMULATIVE % PASSING
1½ in.	0.0	0.0	0.0	100
3/8 in.	24.76	8.82	8.82	91.18
No. 4	7.50	2.67	11.49	88.51
No. 10	7.08	2.52	14.01	85.99
PAN	0.0			
TOTAL	39.34			

### HYDROMETER TEST

ELAPSED TIME (T)	TEMP. °C	HYDROMETER READING (H)	CORRECTED READING (R)	(L)	PARTICLE DIAM. (S)	% SUSPENDED (P)
2	21	26	22	12.7	0.034	30
5	21	24	20	13.0	0.022	27
10	21	24	20	13.0	0.015	22
15	21	22	18	13.3	0.013	24
25	21	19	15	13.8	0.010	20
40	21	19	15	13.8	0.0079	20
60	21	15	11	14.5	0.0066	15
90	21	15	11	14.5	0.0054	15
120	21	12	8	15.5	0.0048	11
1440	21	9	5	15.5	0.0014	6.7

WEIGHT OF SOIL USED IN HYDROMETER TEST (D):  
HYGROSCOPIC MOISTURE CORRECTION FACTOR (G):  
SPECIFIC GRAVITY (ASSUMED):  
DISPERSING AGENT CORRECTION FACTOR (E):  
MENISCUS CORRECTION FACTOR (F):  
TEMP./SPEC. GRAVITY DEPENDANT CONSTANT (K):

65g
0.0984
2.65
3
1
0.01348

#### FORMULAS:

$R = H - E - F$   
 $S = K [ \text{SQRT} (L / T) ]$   
 $P = (R / W) 100$   
 $W = (J \cdot 100) / C$   
 $J = D \cdot G$

SEQUOIA ANALYTICAL

  
Tod Granicher  
Project Manager



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil, H2-VW-3'-3.5'  
Method of Analysis: ASTM D422-63  
Lab Number: 210-0640

Sampled: Sep 3, 1992  
Received: Oct 7, 1992  
Analyzed: Oct 13, 1992  
Reported: Oct 20, 1992

## PARTICLE SIZE DISTRIBUTION BY SIEVE AND HYDROMETER

### SIEVE TEST

- (A) TOTAL WEIGHT OF SAMPLE:  
(B) WEIGHT RETAINED IN NO. 10 SIEVE:  
(C) % PASSING NO. 10 SIEVE:

203.97g
33.37g
88.64

SIEVE TEST FOR  
WEIGHT RETAINED  
IN NO. 10 SIEVE

IDEAL PAN = 0.0  
IDEAL TOTAL = (B)

SIEVE SIZE	WEIGHT RETAINED, g	% RETAINED	CUMULATIVE % RETAINED	CUMULATIVE % PASSING
1½ in.	0.0	0.0	0.0	100
3/8 in.	4.04	1.96	1.96	98.02
No. 4	15.81	7.75	9.73	90.27
No. 10	13.52	6.63	16.36	83.64
PAN	0.0			
TOTAL	33.37			

### HYDROMETER TEST

ELAPSED TIME (T)	TEMP. °C	HYDROMETER READING (H)	CORRECTED READING (R)	(L)	PARTICLE DIAM. (S)	% SUSPENDED (P)
2	21	9	5	15.5	0.038	5.5
5	21	9	5	15.5	0.024	6.5
10	21	8	4	15.6	0.017	5.2
15	21	7	3	15.8	0.014	3.9
25	21	7	3	15.8	0.011	3.9
40	21	7	3	15.8	0.0085	3.9
60	21	6	2	16.0	0.0070	2.6
90	21	5	1	16.1	0.0057	1.3
120	21	5	1	16.1	0.0049	1.3
1440	21	5	1	16.1	0.0014	1.3

WEIGHT OF SOIL USED IN HYDROMETER TEST (D):  
HYGROSCOPIC MOISTURE CORRECTION FACTOR (G):  
SPECIFIC GRAVITY (ASSUMED):  
DISPERSING AGENT CORRECTION FACTOR (E):  
MENISCUS CORRECTION FACTOR (F):  
TEMP./SPEC. GRAVITY DEPENDANT CONSTANT (K):

65g
0.983
2.65
3
1
0.01348

FORMULAS:  
 $R = H - E - F$   
 $S = K [ \text{SQRT} (L / T) ]$   
 $P = (R / W) 100$   
 $W = (J \cdot 100) / C$   
 $J = D \cdot G$

SEQUOIA ANALYTICAL

Tod Granicher  
Project Manager





# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4432  
Sample Descript: Soil, H2-VW-4'-4.5'  
Method of Analysis: ASTM D422-63  
Lab Number: 210-0641

Sampled: Sep 3, 1992  
Received: Oct 7, 1992  
Analyzed: Oct 14, 1992  
Reported: Oct 20, 1992

## PARTICLE SIZE DISTRIBUTION BY SIEVE AND HYDROMETER

### SIEVE TEST

- (A) TOTAL WEIGHT OF SAMPLE:  
(B) WEIGHT RETAINED IN NO. 10 SIEVE:  
(C) % PASSING NO. 10 SIEVE:

228.60g
7.04g
96.92

SIEVE TEST FOR  
WEIGHT RETAINED  
IN NO. 10 SIEVE

IDEAL FAN = 0.0  
IDEAL TOTAL = (B)

SIEVE SIZE	WEIGHT RETAINED, g	% RETAINED	CUMULATIVE % RETAINED	CUMULATIVE % PASSING
1 1/2 in.	0.0	0.0	0.0	100
3/8 in.	0.0	0.0	0.0	100
No. 4	2.50g	1.09	1.09	98.91
No. 10	4.54g	1.99	3.08	96.92
FAN	0.0			
TOTAL	7.04			

### HYDROMETER TEST

ELAPSED TIME (T)	TEMP. °C	HYDROMETER READING (H)	CORRECTED READING (R)	PARTICLE DIAM. (S)	% SUSPENDED (P)
2	21	7	3	15.8	0.038
5	21	7	3	15.8	0.024
10	21	7	3	15.8	0.017
15	21	6	2	16.0	0.014
25	21	5	1	16.1	0.011
40	21	5	1	16.1	0.0086
60	21	5	1	16.1	0.0070
90	21	5	1	16.1	0.0057
120	21	5	1	16.1	0.0049
1440	21	5	1	16.1	0.0014

WEIGHT OF SOIL USED IN HYDROMETER TEST (D):  
HYGROSCOPIC MOISTURE CORRECTION FACTOR (G):  
SPECIFIC GRAVITY (ASSUMED):  
DISPERSING AGENT CORRECTION FACTOR (E):  
MENISCUS CORRECTION FACTOR (F):  
TEMP./SPEC. GRAVITY DEPENDANT CONSTANT (K):

65g
0.995
2.65
3
1
0.01348

FORMULAS:  
 $R = H - E - F$   
 $S = K [ \text{SQRT} (L / T) ]$   
 $P = (R / W) 100$   
 $W = (J \cdot 100) / C$   
 $J = D \cdot G$

SEQUOIA ANALYTICAL

*Tod*  
Tod Granicher  
Project Manager

Engineering Science, Inc.

SAMPLE DESCRIPTION:

LABORATORY NUMBER: 210-0637

U.S. STANDARD SIEVE SIZES

59%


SAND

27%

SILT

6%


CLAY



SAMPLE DESCRIPTION: Engineering Science, Inc.

LABORATORY NUMBER: 210-0638

U.S. STANDARD SIEVE SIZES




GRAIN DIAMETER IN MILLIMETERS

COARSE	FINE	COARSE	MEDIUM	FINE	SILT SIZES	CLAY SIZES
GRAVEL		SAND			FINES	

PERCENT PASSING BY WEIGHT

LABORATORY NUMBER: 210-0639

U.S. STANDARD SIEVE SIZES



GRATIN DIAMETER IN MILLIMETERS

BOBBLES	GRAVEL		SAND			FINES	
	COARSE	FINE	COARSE	MEDIUM	FINE	SILT SIZES	CLAY SIZES






SAMPLE DESCRIPTION: Engineering Science, Inc.

LABORATORY NUMBER: 210-0641


U.S. STANDARD SIEVE SIZES

SAND	76%
SILT	21.5%
CLAY	1.5%



LABORATORY NUMBER: 210-0642

Year	1990	2000	2010	2020	2030	2040	2050	2060	2070	2080	2090
Population (millions)	5.3	5.5	5.7	5.9	6.1	6.3	6.5	6.7	6.9	7.1	7.3
GDP (trillion USD)	1.5	2.5	4.0	6.0	9.0	13.0	18.0	24.0	31.0	39.0	48.0
Life expectancy (years)	47	52	57	62	67	72	77	82	87	92	97
Urban population (%)	20	30	40	50	60	70	80	90	95	98	100
Renewable energy (%)	10	15	20	25	30	35	40	45	50	55	60
CO2 emissions (Gt)	15	20	25	30	35	40	45	50	55	60	65
Forest cover (%)	30	28	26	24	22	20	18	16	14	12	10
Water stress (%)	10	15	20	25	30	35	40	45	50	55	60
Healthcare spending (GDP %)	5	7	9	11	13	15	17	19	21	23	25
Education spending (GDP %)	3	4	5	6	7	8	9	10	11	12	13
Research & Development (GDP %)	2	3	4	5	6	7	8	9	10	11	12
Unemployment (%)	10	12	14	16	18	20	22	24	26	28	30
Income inequality (Gini index)	40	42	44	46	48	50	52	54	56	58	60
Gender inequality (GII)	0.75	0.78	0.81	0.84	0.87	0.90	0.93	0.96	0.99	1.00	1.00
Human Development Index (HDI)	0.55	0.65	0.75	0.85	0.95	1.00	1.00	1.00	1.00	1.00	1.00
Life expectancy (years)	47	52	57	62	67	72	77	82	87	92	97
Healthcare spending (GDP %)	5	7	9	11	13	15	17	19	21	23	25
Education spending (GDP %)	3	4	5	6	7	8	9	10	11	12	13
Research & Development (GDP %)	2	3	4	5	6	7	8	9	10	11	12
Unemployment (%)	10	12	14	16	18	20	22	24	26	28	30
Income inequality (Gini index)	40	42	44	46	48	50	52	54	56	58	60
Gender inequality (GII)	0.75	0.78	0.81	0.84	0.87	0.90	0.93	0.96	0.99	1.00	1.00
Human Development Index (HDI)	0.55	0.65	0.75	0.85	0.95	1.00	1.00	1.00	1.00	1.00	1.00

[illegible]

## CHAIN OF CUSTODY RECORD FOR WATER SAMPLES

20206-4180  
Sawyer - Bessie  
1941/98 - 1941/98  
1941-98 - 1941-98  
1941-98 - 1941-98





**Battelle**

Columbus Laboratories

Proj. No.

54468-0640

Project Title  
Bioventing

HANSCOM AFB

SAMPLERS: (Signature)

*Doug Hendry / Jim Abbott*

DATE

TIME

SAMPLE I.D.

02 OCT 92

H1-VW-4'-4.5'

02 OCT 92

H1-VW-4'-4.5'

02 OCT 92

H1-VW-4'-4.5'

02 OCT 92

H1-VW-4.5'-5.0'

02 OCT 92

H1-VW-4.5'-5.0'

02 OCT 92

H1-A-3'-4'

02 OCT 92

H1-A-3'-4'

02 OCT 92

H1-A-3'-4'

03 OCT 92

H2-VW-3'-3.5'

03 OCT 92

H2-VW-3'-3.5'

03 OCT 92

H2-VW-4'-4.5'

03 OCT 92

H2-VW-4'-4.5'

04 OCT 92

H1-BKG-2.5'-3'

04 OCT 92

H1-BKG-2.5'-3'

04 OCT 92

H1-BKG-3'-3.5'

Relinquished by: (Signature)

*Doug Hendry*

Date/Time

04 OCT 92 2200

Received by: (Signature)

Relinquished by: (Signature)

Date/Time

Relinquished by: (Signature)

Date/Time

Received by: (Signature)

Relinquished by: (Signature)

Date/Time

Received for Laboratory by: (Signature)

*Jim Abbott*

Relinquished by: (Signature)

Date/Time

10/26/92

Relinquished by: (Signature)

Date/Time

0930

Received by: (Signature)

Remarks

SEND RESULTS TO: BATTTELLE

JEFF K: H EL

505 KING AVE,

(Columbus) OH

10/26/92

10/26/92

10/26/92

SAMPLE TYPE (V)

BTX and TPH

Total Soil Moisture

Iron

Alkalinity

pH

Soil Analysis

total Phosphate

total Nitrogen

total

Container No.

Number of Containers

Remarks

4oz GLASS

16oz GLASS

BRASS TUBE

4oz GLASS

16oz GLASS

BRASS TUBE

4oz GLASS

16oz GLASS

BRASS TUBE

4oz GLASS

16oz GLASS

BRASS TUBE

4oz GLASS

16oz GLASS

BRASS TUBE

JOB No. Engineering-Science JOB No. V.E 060003

CHAIN OF CUSTODY RECORD

Form No.

001

**APPENDIX C**  
**BUILDING 1639 SOIL GAS PERMEABILITY DATA**

Table C-1. Results of Soil Gas Permeability Test at Monitoring Point H1-MPA

Time (min)	Pressure ("H <sub>2</sub> O) by Depth		Time (min)	Pressure ("H <sub>2</sub> O) by Depth	
	2.5'	5.0'		2.5'	5.0'
0	0	0.01	20	0.025	0.32
1	0.05	0.17	23	0.025	0.33
2	0.02	0.21	26	0.025	0.34
3	0.02	0.22	29	0.03	0.35
4	0.03	0.225	32	0.025	0.35
5	0.033	0.235	35	0.03	0.35
6	0.35	0.25	38	0.025	0.35
7	0.03	0.27	41	0.025	0.35
8	0.02	0.28	44	0.02	0.35
9	0.02	0.30	47	0.02	0.35
10	0.015	0.30	50	0.03	0.35
12	0.01	0.30	60	0.02	0.35
14	0.02	0.30	70	0.02	0.36
16	0.02	0.30	80	0.01	0.37
18	0.03	0.32	90	0.02	0.36

Table C-2. Results of Soil Gas Permeability Test at Monitoring Point H1-MPB

Time (min)	Pressure ("H <sub>2</sub> O) by Depth		Time (min)	Pressure ("H <sub>2</sub> O) by Depth	
	2.5'	5.0'		2.5'	5.0'
1	0.045	0.01	12	0.080	0.015
2	0.06	0.02	50	0.115	0.025
3	0.065	0.01	55	0.115	0.025
4	0.07	0.015	60	0.110	0.02
5	0.075	0.02	70	0.115	0.02
6	0.075	0.02	80	0.113	0.02
7	0.090	0.015	90	0.110	0.022
8	0.092	0.015			
9	0.095	0.02			
10	0.085	0.02			

Table C-3. Results of Soil Gas Permeability Test at Monitoring Point H1-MPC

Time (min)	Pressure ("H <sub>2</sub> O) by Depth		Time (min)	Pressure ("H <sub>2</sub> O) by Depth	
	3.5'	6.0'		3.5'	6.0'
0	0	0	20	0.01	0.02
1	0	0.01	23	0.02	0.015
2	0.01	0.015	26	0.03	0.035
3	0.01	0.03	29	0.03	0.015
4	0.02	0.02	32	0.02	0.02
5	0.03	0.025	35	0.025	0.015
6	0.02	0.03	38	0.015	0.02
7	0.03	0.01	41	0.025	0.15
8	0.01	0.015	44	0.01	0.01
9	0.015	0.005	47	0.005	0.015
10	0.01	0.02	50	0.02	0.04
12	0	0	60	0.01	0.02
14	0.02	0.01	70	0.01	0.015
16	0.015	0.025	80	0.01	0.01
18	0.03	0.02	60	0.015	0.01

**APPENDIX D**  
**BUILDING 1639 IN SITU RESPIRATION TEST DATA**





Figure D-1. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point H1-MPA-5.0'



**Figure D-2. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point H1-MPB-2.5'**







Figure D-3. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point H1-MPB-5.0'



**Figure D-4. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point H1-MPC-6.0'**

**APPENDIX E**  
**BUILDING 1812 SOIL GAS PERMEABILITY DATA**

Table E-1. Results of Soil Gas Permeability Test at Monitoring Point H2-MPA

Time (min)	Pressure ("H <sub>2</sub> O) by Depth		Time (min)	Pressure ("H <sub>2</sub> O) by Depth	
	2.5'	5.0'		2.5'	5.0'
0	0	0	20	0.55	0
2	0.50	0	25	0.55	0
3	0.54	0	30	0.56	0
4	0.55	0.005	35	0.56	0
5	0.55	0	40	0.56	0
6	0.55	0	50	0.57	0
7	0.55	0	60	0.58	0
8	0.55	0	75	0.58	0
9	0.55	0	90	0.59	0
12	0.55	0			
16	0.55	0.55			
18	0.55	0			

Table E-2. Results of Soil Gas Permeability Test at Monitoring Point H2-MPB<sup>1</sup>

Time (min)	Pressure ("H <sub>2</sub> O) by Depth		Time (min)	Pressure ("H <sub>2</sub> O) by Depth	
	2.5'	5.0'		2.5'	5.0'
0	0	0	14	0.01	0.01
1	0	0	16	0	0.005
2	0	0	18	0.005	0.005
3	0	0.005	20	0	0
4	0	0	25	0	0
5	0	0	30	0.005	0.005
6	0	0	35	0	0
7	0	0	40	0.005	0.005
8	0	0	50	0.005	0.005
9	0	0	60	0.005	0.005
10	0	0	75	0.005	0.005
12	0.005	0.005			

<sup>1</sup> Pressure readings were not collected from monitoring point H1-MPB-7.0'.

Table E-3. Results of Soil Gas Permeability Test at Monitoring Point H2-MPC

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	2.5'	4.5'	6.0'		2.5'	4.5'	6.0'
1	0	<0	<0	16	0	<0	<0
2	<0	<0	0	18	0	<0	<0
3	<0	<0	<0	20	0	<0	<0
4	<0	<0	<0	25	0	<0	<0
5	<0	<0	<0	30	0	0	0
6	0	<0	<0	35	0	0	0
7	0	<0	<0	40	0	0	0
8	0	<0	<0	50	0	0	0
9	0	<0	<0	60	0	0	0
10	0	<0	<0	70	0	0	0
12	0	<0	<0	80	0	0	0
14	0	<0	<0	90	0	0	0